INDEX OF TREE-RING DATED BUILDINGS IN ENGLAND
NATIONAL LIST approximately in chronological order, revised to VA51 (2020).

© Vernacular Architecture Group 2021
These files may be copied for personal use, but should not be published or further distributed without written permission from the Vernacular Architecture Group.
Always access these tables via the VAG website. Unauthorised copies released without prior consent on search engines may be out of date and unreliable.
Since 2016 a very small number of construction date ranges from historical sources have been added. These entries are entirely in italics.
Before using the index you are recommended to read or print the *introduction and guidance*, which includes a key to the abbreviations used on the tables.

1600 -1649

Place holder	Felling date range	County-historic (later)	Placename	Address	VA ref; HE ref; (other ref)	Description / keywords	NGR
1600	1599/1600	Berks	Holyport	Lynden Barn	41.86 *HOLB/17/09*	3-bay barn, jowled posts, straight braces, *queen strut* roof largely replaced	TQ 895777
1600	1600 *c.*	Leic	Leicester	Castle	15.66 Notm	East gatehouse. Repairs or rebuilding. (Also see 1152).	SK 582041
1600	1600	Leic	Market Bosworth	Coton Priory Farm, Coton Lane	39.108 Notm	In main range, short *curved upward braces* in wall frame. *Interrupted tiebeam* with '*queen studs*' to collar. Tiebeam & collar W truss has 4 struts. In 2-bay wing, *square panel framing*, tiebeam & collar with 3 struts.	SK 394024
1600	1584 -1619	Leic	Walton-on-the-Wolds	10 Loughborough Road	23.53 Notm	*Close-studded*	SK 592199
1600	1600 +	Notts	Newark-on-Trent	17 Boar Lane	30.97 Notm	Re-used roof timbers, also of 1658 (qv).	SK 797539
1600.	1600 *c.*	Notts	Nuthall	Hempshill Hall, Low Wood Road	38.111 Notm	Mantle over hall fireplace felled *c.*1600. (Also see 1497).	SK 514445
1600.	1600 *c.*	Notts	Waleswood	Limetree Cottage	13.49 Sh	Cruck truss now in Doncaster Museum	SK 457834
1600	1595/6 - 1600	Oxf	Sydenham	Cooper's Yard Musgrave Farm	42.90 SYCY/12/10	Barn. Gabled. Rectangular panels, mid-rails. Jowled posts. Curved braces. Tiebeams, principals, raking struts.	SP 729017
1600	1599 ? & 1600 ?	Oxf	Wheatley	The Manor House	46.112 Oxf	Crosswing (with a 1601 plaster date plaque on N gable). (For reconstruction of main range see 1624).	SP 594058
1600	1600 *c.*	Shrop	Market Drayton	Cotton's Hse, Shropshire St	36.93 Oxf	*Box-framed*. E-plan, baffle entry. *Close studding*. *Cusped down-braces*. *Jettied* attic with one row of *square panels* in front wall. Tiebeam & collar trusses, single tier side purlins *straight windbraces*.	SJ 673339
1600	1600	Staffs	Ford	Old School House	28.128 Notm	Cruck. Stone walls from outset (datestone 1605); apex type C - *yoke* supports ridge.	SK 063540
1600	1598 /99 1600	Surr	Limpsfield	Tenchleys Manor	38.103 *LITM/22/06*	Moated. Parlour wing. *Gabled*. *Dropped tiebeams*, in-line *tenoned purlins*.	TQ 421509
1600	1600 *c.*	Wilts	Avebury	Avebury Manor (N.Trust)	43.93 Notm	E range (south extension) roof and S range (upper and lower) roofs. (For E range ceiling see 1557 *c.*)	SU 098699
1600	1596 -1623	Worcs	Bewdley	41 Load Street	48.104 IT	Re-used carved jetty bressumers.	SO 785753
1600	1600 *c.* ?	Worcs	Droitwich	46 High Street	48.108 IT	1575 +, but *c.*1600 suggested. 1st and 2nd floors jettied with carved brackets. Gables retain quadrant bracing in small square panels.	SO 901633
1600	1600 +	YksWR (YksS)	Arksey	Stockbridge Farm	11,22 Sh	Farmhouse, no roof details.	SE 574066
1601	1601	Cumb	Brampton	Scarrow Hill	43.88 Notm	Stone walls, gabled slate roof. 4 bays, 2 storeys. Tiebeam and collar, principals, 'back purlins'.	NY 569618
1601	1588 -1613	Leic	Diseworth	13 Hall Gate	39.123 Notm	Southern barn of 2. Cruck blades, *tiebeam*, *collar*, *yoke*: single tier of side purlins. Also see 1671 /2.	SK 451245
1601	1598 +5	Notts	Beckingham	Thistle Farm	15.67 Notm	No roof details.	SK 782900
1601	1598 +5	Notts	Cropwell Bishop	24 Fern Road	16.40 Notm	*Box-framed* cottage.	SK 687355

1601	1569 -1601	Oxf	Henley-on-Thames	Tudor House, 49 Duke Street	39.139 Oxf	Cross-wing? 1½ storeys, *jettied* front and rear, *gabled*. *Arch-braced* tiebeam & collar, *crown strut*, clasped purlins, *curved wind braces*.	SU 761825
1601	1601	Shrop	Shrewsbury	The Orrel (next to Bear Steps)	28.160 Oxf (1)	Arcade. *Close studding with mid-rail*. *Long straight down-braces*. Tiebeam and collar with 3 struts, *V-struts*. Also see 1358/9.	SJ 493125
1601	1583 -1618	Staffs (WMid)	West Bromwich	Hill House	21.38 Notm	No roof details.	SP 013922
1601	1601 1598 -1603	Sus W	Rudgwick	Warhams, Naldretts Lane	40.123 Oxf	Inserted re-used ceiling in hall of 1213 -39 (*qv*).	TQ 088323
1602	1589 -1615	Ches	Malpas	Overton Hall	29.113 Oxf	Also 1595-1625. Moated. Wing. Jowled posts, 'spur-ties' deep-swinging arch-braces with *slip tenons*.	SJ 471484
1602	1591 -1616	Cor	Mousehole	Keigwin Place	40.111 Notm	Ground floor ceiling beams.	SW 469263
1602	1602 +0	Derbs	Brampton Frith	Hall Farm, Frithall Lane	24.43 Notm	Cruck: *yoke*, *collar*, *tiebeam*, Apex types L1 & D	SK 331709
1602	1601 /02	Dev	Barnstable	The Exeter Inn, Litchdon St	44.86 *EXEI/04/12*	Inn. Front range is a 4-bay 2-storey end-chimney building. Gabled slate roof. Principals, lap-jointed collars, 2 tiers of purlins + ridge piece.	SS 560328
1602	1597 1598 -1606	Dors	Charminster	Wolferton House	37.119 Oxf (2) CfA 55/2005	Riding House. A very early example. (Roof timbers dated to 1720 *qv*).	SY 679923
1602	1601 /02	Hamps	Tunworth	Beechcroft	31.104 Oxf	Lobby entry. *Small-panel* framing with *straight braces*. Tiebeam & collar, *queen strut*, clasped purlin. (Also see 1686 /87).	SU 673485
1602	1602	Heref	Vowchurch	White House	31.116 UoW	Third phase of house (first built *c.* 1540 *qv*).	SO 349357
1602	1588 -1616	Kent	Sevenoaks	21-25 London Rd	19.49 Notm	Rear wing. (Also see VA39.107).	TQ 529548
1602	1601 /02	Lancs	Horwich	Building 1, Sefton Fold	25.25 Sh	No roof details.	SD 648097
1602	1589 -1614	Lancs (GrMan)	Middleton (Nr Rochdale)	Tonge Hall, William St.	46.98 Notm RRS 43/2014	Large timber-framed house. Walls inc. decorative quatrefoil panels, coved jetties, projecting gables. Principal rafter trusses with tiebeams and raking queen struts. 2 tiers of side purlins. (Also see 1640 -65).	SD 877058
1602	1594 +15	Notts	Mansfield Woodhouse	'Priory'	18.53 Notm	No roof details.	SK 537632
1602	1602	N'umb	Morpeth	Cockle Park Tower, Hebron	41.99 Notm RDR 44/2009	16thC tower house with barrel vault. On upper floor, 5 tiebeam and lapped collar trusses, *trenched purlins*.	NZ 201912
1602	1601 1602	Oxf	Henley on Thames	The King's Arms, 32-6 Market Place	31.94 Oxf	Stables. Upper floor domestic but unheated?	SU 759826
1602	1602	Oxf	Ewelme	Cottesmore Farm	28.165 Oxf	Small barn. Tiebeam & collar. *Raking struts clasp lower purlins*: *queen struts clasp upper purlins*. *Bridled scarf joints* on the purlins.	SU 635922
1602	1601 /02	Surr	Milford	Chimneys	38.103 *MICH/17/06*	3½ bay *end smoke-bay* house. *Queen struts*, clasped purlins, *curved wind braces*. Timbers with felling date range of 1507-34 were either re-used, or an earlier phase.	SU 939423
1602	1601 /02	Surr	Ockham	Bridgefoot Barn	39.115 *RIBB/20/07*	The eastern of 2 adjoining barns. 3 bays with front and rear outshots. *Gabled*. *Queen struts*, clasped purlins, straight wind braces. (For W barn see 1636 *c.* 1639. For the farmhouse see 1633 /34).	TQ 056569
1602	1601 /02	Sus E	Ticehurst	Old Farm, Dale Hill	46.93 *TNOF/18/14*	2½ bay central chimney house. Small square panel wall frame. ?'The roof is of clasped purlin construction with 1 tier of in-line butt purlins.'? (Also re-used timbers of 1503 & 1540 -71).	TQ 698305
1602	1584 -1620	YksNR (YksN)	Thornton le Dale	Roxby Farm Cottage, Malton Gate	40.121 DCL	Cruck truss, *saddle*, *collar*, *ridge purlin* standing on *king post* (Apex type F1).	SE 833828
1603	1592 -1614	Lon	Hillingdon	The Old Coach House, Eastcote	43.90 Notm RDRS 8/2012	2-storeys, timber-framed. Braced tiebeams, principals, collars, queen struts, windbraces. (For gallery floor see 1833 -58).	TQ 107888
1603	1602 1603	Lon	Tower Hamlets	Tower of London	28.164 Oxf	White Tower: arcade posts, beam and ceiling joists in West Chamber.	TQ 336805
1603	1602 1603	Nort	Towcester	181 Watling St	42.106 Oxf	2-bay, lateral stack. Close studding. Tiebeams, diminished principals with bridle joints, 2 collars, 2 tiers of threaded purlins.	SP 693486
1603	1603	Shrop	Cound	Fulway Cottage	25.31 Oxf	Single-cell building? (Upper floor timbers felled 1639)	SJ 553036

1603	1601 /02 1603	Shrop	Shrewsbury	165 Frankwell	32.81 Oxf	*Jettied gable*. Tiebeam & collar, *queen struts*.	SJ 489128
1603	1587 -1619	Surr	Ockham	Ashlea and Church Gate Cottage	39.115 *OKAC/05/07*	Floor, and probably smoke hood (inserted into hall of 1468 /69 *qv*).	TQ 069566
1603	1602 /03	Surr	Thursley	Ridgeway Farm	38.105 *THRI/02/06*	Floor (inserted into hall of 1436 *c. qv*).	SU 891385
1603	1546 -71 1590 -1615	Worcs	Naunton Beauchamp	Naunton Court	39.126 Notm	This date is for the N-S range. *Box framed*: *close studding* and *square panels*. Principal rafter and *collar* trusses. (E-W range was dated 1583+).	SO 957524
1603	1603	Worcs	Redditch	Meadow Farm	38.125 Oxf	S and E wing upper floors. Also see 1439 -69: 1598 (granary)	SP 042693
1603	1582 -1623	YksWR (YksW)	Wakefield	Little Westgate	23.46 Sh	Timbers from demolished building.	SE 332208
1604	1591 -1616	Cor	Mousehole	Keigwin Place	40.111 Notm	Ground floor ceiling beams.	SW 469263
1604	1603 /04	Ess	Cressing Temple	Cressing Farmhouse	28.141 Sh	No roof details.	TL 799187
1604	1603 1604	Hamps	Bentworth	Hall Place	39.135 Oxf	Front *gable* roof, *inserted floors* ... Stone chimney inserted at low end of hall, forming a lobby entry plan. (Also see 1248, 1295 -1327, 1520).	SU 663399
1604	1604 *c.*	Hamps	Hook	Murrell, Totters Lane	51.119 RGMU/01/19	Tiebeam (and chimney insertion?) into house with primary phase of 1584 /85 (qv).	SU 746550
1604	1588 -1620	Hamps	Sparsholt	Deane Cottage	44.87 *SODC/28/12*	Chimney & ornately-moulded ceiling beams inserted into hall house (of 1498 *qv*).	SU 443310
1604	1604 +	Heref	Hereford	102 East Street	28.144 Sh	Floorboards.	SO 510400
1604	1603 /04	Suff	Bedfield	Bedfield Hall	38.123 Oxf	Rear part of west wing roof. (Also see 1420, 1618, 1625 /6 1628).	TM 227264
1604	1591 -1616	YksWR (YksN)	Conistone with Kilnsey	Scar Laithe	51.135 Notm	Stone barn. 4 roof trusses all have redundant joints indicating re-use of up to 5 cruck trusses. (Other dates in this entry – 1504+, 1724).	SD 975680
1605	1587 -1622	Derbs	Heathcote	Hill Top Farm	23.52 Notm	Cruck	SK 146602
1605	1605 *c*.	Derbs	Shardlow	Great Wilne Farm, Great Wilne	25.41 Notm	2-phase brick threshing barn. Staggered purlins, wind braces, high *collar* ... (Re-used timbers of Spring 1435).	SK 448309
1605	1603 /04 1604 /05	Heref	Dinmore	Dinmore Manor	31.92 Oxf	*Queen struts*: 'queen post' [?]: side purlins.	SO 486502
1605	1604 /05	Kent	Sevenoaks	Knole (NT)	41.104 Oxf	a. Orangery roof: no details. b. Retainer's gallery roof: no details	TQ 539542
1605	1592 -1617	Nort	Weston	Armada House, High Street	49.129 Notm	Significant fire damage. Two ranges at right-angle. This dating is for north range roof. (For north range ground-floor ceiling see 1487 -1512. Also see 1566 -91 and 1640).	SP 591468
1605	1578 + 1605	Suff	Debenham	The Buck's Head, 27 High Street	35.94 Notm (3) CfA 41/2003	Grandstand / standing galleried on both sides. (Also see 1600 -25, 1620).	TM 173632
1605	1605	Surr	Nutfield	Doggetts, Coopers Hill Road	51.121 *RHDO/39/19*	Gabled, 2½ storeys, end smoke-bay. Raking queen struts, clasped side purlins, straight wind braces. (For front range see 1564 /65).	TQ 317484
1605	1604 /05	Sus W	Kirdford	Butts Cottage	39.116 *PEBC/08/07*	2½ bay *smoke bay* house. Unjowled wall posts and *large panel* framing. *Gabled*. Clasped purlins.	TQ 016267
1605	1600 -1610	Worcs	Bewdley	Bailiff's House	11.34 Sieb (4)	'The first building in England to be dated by dendrochronology' (in 1969).Inscribed date T 1610 B. 2½ storeys, *jettied*, *close studding*, *small square decorative panels*, *ovolo-moulded mullion and transom windows*. *Interrupted* tiebeam and collar trusses, 2 tiers of *side purlins*, *ridge purlin*.	SO 786753
1605	1605	YksWR (YksW)	Thornton	Headley Hall Farm Upper Headley	32.92 Sh CfA 10/2001	East Barn. *Stone*. Three bays. King post roof. (Also see 1583?)	SE 097321
1606	1605 /06	Hamps	Ashley	The Old Manor	28.175 Oxf (5)	House. Timber-framed. Floor inserted into open hall. (Also see 1520 and 1529 /30).	SU 384311
1606	1605/06	Kent	Sevenoaks	Knole (NT)	41.104 Oxf	a. South Barracks roof. b. King's Tower ceiling.	TQ 539542
1606	1592 -1620	Kent	Woodchurch	22 -26 Front Road	45.102 *TNFR/22/13*	Originally timber-framed, now brick & much-rebuilt.	TQ 942348
1606	1583 -1628	Lon	Enfield	17 Gentlemen's Row	28.136 MB AML 97/97.	Close-studded tiebeam and collar roof truss and clasped purlins in added bay. (For earlier phase see 1465 -1494).	TQ 325978

1606	1603 +5	Notts	Skegby	Old Road	15.68 Notm	Barn: cruck. (Also see 1613).	SK 499609
1606	1596 -1616	Shrop	Aston Eyre	Hall Farm	29.122 Oxf	Gatehouse extension. *Box framed*. (Also see 1341 -1352).	SJ 666202
1606	1605 -06	Sus W	West Chiltington	Nyetimber Farm, Gray St.	42.104 Notm RDR 36-2010	South barn. *Timber-framed*, *hipped*. Side walls have 3 studs & girding beam to each bay; *curved down-braces*, *weather-boarded* below, *daub-filled* above. *Arch-braced tiebeams, raked struts to principals.*	TQ 084194
1606	1591 -1621	Warks	Erdington	The Lad in the Lane, Bromfield Lane	*MPHE* ERD-A 38.124 Oxf	Hall partitioned (also floor inserted into 1 bay?). (For hall see 1400, for N wing see 1456 -61).	SP 112907
1606	1594 -1617	YksNW (YksN)	Thornton le Street	Calvis Hall	51.130	Rear block, stone. Ceiling beam. (Also a re-used collar of 1466d).	SE 420845
1606	1606	YksWR (YksS)	Cleckheaton	Westroyd, Hunsworth Lane	44.96 Notm	Wing. Tiebeam, king post, principals, single tier side purlins + ridge beam. (For main range see 1404).	SE 189272
1607	1579 & 1594 -1619	Dur	Ovington	Girlington Hall Farmhouse	51.104 51.106 Notm RRS 79/2019	Present hall includes 3 tiebeam and principal trusses with slender raking struts. Elements relating to remodelling include purlins 1579, ground-floor ceiling frame 1579, first-floor ceiling frame 1435 -36 & 1579. Other dates include 1594 -1619, and also see 1696 -1709 *cal*. (For earlier hall roof see 1436; for wing see 1439, 1440).	NZ 128137
1607	1605 /06 1606 /07	Ess	Manuden	Battles Hall, Maggotts End	37.119 Oxf	Moated. *Box-framed*. *Hipped roof*. Common *rafters are tenoned* into side purlins [as at Harlaston Manor, Staffs].	TL 476277
1607	1599 -1614	Hamps	Boarhunt	Bere Farmhouse, North Boarhunt	38.126 Oxf	Large *brick* building. Lobby entry with back to back chimney. *Tenoned purlins*.	SU 596095
1607	1606 /07	Hamps	Headley	Mellow Farm, Dockenfield	32.79 Oxf	2½ bays. Lobby entry: back-to-back chimney in central ½ bay. *Small panel framing*. *Tiebeams*, *queen struts*, clasped purlins.	SU 831389
1607	1607	Hamps	Odiham	Poland Farm	40.126 Oxf	House. 2 primary bays + 1 secondary. Tiebeams, *queen struts*, clasped purlins.	SU 745526
1607	1606 -07	Shrop	Ruckley & Langley	Langley Gatehouse	24.47 Sh	Samples from off-cuts.	SJ 539002
1607	1603 /04 1606 /07	Shrop	Wem	Tilley Manor	48.93 *SYTB/11/16*	E. Wing with lateral chimney. Single bay with queen strut roof, 2 tiers trenched purlins. (For main range see1568 and for W wing see 1601 -31.	SJ 506279
1607	1601 -12	Suff	Debenham	Broadway House, 19 High Street	40.131 MB	3 bays, 2 storeys + attic.	TM 173633
1607	1607	Surr	Newdigate	Nyes Place, Rusper Road	35.82 *NEPN/39/03*	3½ bay integral chimney house. *Half-hipped* roof, Horsham stone. *Curved down-braces* in end walls. *Dropped tiebeams* for attic floor.	TQ 201400
1607	1607	Sus E	Chaily	1, Coppard's Bridge	46.93 *BNCB/23/14*	Succeeds VA 43.98. Single bay added to primary dwelling (of 1472/73 *qv*). (For reconstructed roof see 1715).	TQ 400195
1607	1607	Sus W	Rudgwick	Warhams, Naldretts Lane	40.123 Oxf	N extension to wing of 1548 /9 (*qv*) ...	TQ 088323
1608	1608	Cumb	Moorhouse	Moorhouse Farm	29.109 Notm	Barn. Cruck.	NY 330585
1608	1579 -1604 1595 -1620	Cumb	Strickland Roger	Burneside Hall	51.124 Notm RRS 51/2019	Hall. Raked struts from tiebeams to principals, cranked collars, 2 tiers side purlins. Partition 1582-1607. Stairs 1605 -30. (For wing truss 5 see 1478-1503, for wing trusses 3 & 4, 1612 -37. For gatehouse roof trusses see 1584-1609).	SD 509959
1608	1607 /08 **i**	Glouc	Yate	Goosegreen Farmhouse	50.89 Swan 009	Farmhouse with contemporary wall paintings.	ST 711838
1608	1607 /08	Oxf	Mapledurham	1-2 Hodmore Farm Cottages	37.126 Oxf	*Box framed*. (Also a re-used timber felled 1474 /75).	SU 684781
1608	1607 -08	Oxf	Mapledurham	New Farm	26.65	Third Barn. Re-used *square-panel* frame. (Now at Chiltern Open Air Museum).	SU 679757
1608	1608	Oxf	Mapledurham	St Margaret's Church – tower	38.130 Oxf	*Brick* and *flint* tower, dated from tiebeams re-used as ceiling beams in tower heightening of 1862 1863 (*qv*). (For nave roof see 1445 /46).	SU 670767
1608	1607 /08 1608	Shrop	High Ercall	High Ercall Hall	33.98 Oxf	Stone and brick. L-shaped plan. Over main range, principal rafters, straight soulaces & ashlars. W end of N range has 3 upper cruck trusses.	SJ 595173
1608	1607 /08	Som	Goathurst	Halswell House	50.98 *THKH/17/18*	Felling date of wind brace in east range. (For south range see 1590).	ST 253 337
1608	1608	Som	Halse	Stoford	28.173 Oxf	Solid tread stairs. (Jointed cruck failed to date).	ST 144288

1608	1604 /05 1608 c.	Surr	Artington	Littleton Farmhouse, Littleton Lane	46.92 *GULH/16/14*	3½ bay central chimney house of '2 storeys and integral attic'. Small square panels, down-braces. Unjowled posts. Gabled roof has clasped purlins and diminished principals, queen struts. (Kitchen wing dated to 1606d).	SU 981473
1608	1606 1607 /08	Surr	Newdigate	Reffolds	37.102 *NERE/17/05*	Main range comprising a hearth bay and a service bay: *continuous front jetty*. *Gabled* roof with *raking struts* and clasped purlins. The parlour wing of timber felled 1610/11 (*qv*).	TQ 200432
1608	1607 /08	Surr	Ockley	Black and White Cottage	35.83 *OCBW/33/03*	2½ bay central *smoke bay* cottage. *Gabled*. Walls include down-braces and unjowled posts. *Tiebeams [& collars ?*], *queen struts*, clasped purlins. (One tiebeam was of re-used timber felled 1502-34. Chimney inserted 1690 /91 *qv*).	TQ 130387
1609	1608 /09	Dur	High Coniscliffe	Ulnaby Hall	41.91 Sh RDR 61/2009.	West wing. Tiebeam, high short collar; 3 *'threaded' purlins* and a *threaded ridge-purlin*. No wind braces.	NZ 226172
1609	1608 /09	Ess	Coggeshall	'Spooners', 30 Church St	43.95 IT (6)	For rear extension see 1608/9. Rear parlour / solar extension: Roof has wind-braced side purlins, (For front range see 1353-86).	TL 851226
1609	1607 -1610	Hamps	Kings Worthy	Old Farm Cottages, Abbots Worthy	36.97 Oxf	*Box-framed*. Parlour, hall [but was it open?], and *end smoke bay*. *Jettied* and *gabled* wings to rear built with timber felled 1610.	SU 497326
1609	1608 /09	Hamps	Tichborne	The Old Post Office	32.80 Oxf	3(?) bays: lobby entry, back-to-back chimney. *Jettied*. *Tiebeam*, *queen strut*, clasped purlin.	SU 571304
1609	1607 /08 - 1610	Oxf	Chalgrove	2 Mill Lane, The Lamb	46.109 Oxf	3 bays, lobby entry. Tiebeam, princess struts, clasped purlins.	SU 631972
1609	1607 1609	Oxf	Oxford	Merton College	38.130 Oxf RDR 80/2006.	Fellow's Quadrangle. Recorded as built Sept 1608 – September 1610. No tiebeams, but 2 collars, with a *wide king strut*, and 2 *raking struts*. 2 tiers of purlins. (Also see 1694).	SP 517060
1609	1609	Shrop	Cardington	Shootrough	27.103 Oxf	Wing. *Jettied* gable. For hall range see 1422.	SO 490964
1609 +	1609 +	Som	Norton St Philip	Farleigh Hungerford Castle	34.94 MB CfA 68/2002	St Annes' Chapel: painted beams. (Also a window lintel of 1807 -39).	ST 801577
1609	1608 1608 /09	Suff	Debenham	23 & 25 High Street	40.131 MB	Re-roofing of rear range (to building of 1417 /18 *qv*)	TM 173632
1609	1609	Suff	Wickham Market	Letheringham Lodge	45.118 Oxf	Replacement roof of 2½ bays: principals, 2 tiers of tenoned side purlins, formerly windbraced. Date on door lintel 'EW 1610'. (For earlier phase see 1472 -75).	TM 276570
1609	1608 /09	Surr	Newdigate	Home Farm: South Barn	30.89 MB AML 37/98	Barn. Addition to W end of barn (of 1411 -22 *qv*).	TQ 206406
1609	1609	Surr	Nutfield	King's Mill House, South Nutfield	41.89 *NUKM/06/09*	*Small square panels*, no braces. *Gabled* roof has *queen struts*, clasped purlins, and *straight wind braces*.	TQ 298491
1609	1607 *c.* 1608 /09	Surr	Wrecclesham	The Royal Oak	39.119 *FARO/17/07*	4½ bay *central smoke bay* house incorporating an open hearth service bay. Jowled posts and *curved braces* in walls. *Half-hipped* roof. Tiebeam & collar, *3 struts*, clasped purlins, *curved wind braces*.	SU 824447
1609	1609 +	Worcs	Droitwich	Star Yard, 15 -17 High Street	48.107 IT	Rear range. (For front range see 1513).	SO 899633
1609	1596 -1621	YksWR (YksN)	Horton in Ribblesdale	Stubbing Barn, Low Birkwith	51.136 51.84 Notm	Purlins in a roof containing re-used former crucks.	SD 798768
1610 *c.*	1610 *c.*	Derbs	Melbourne	56 Potter St	44.92	Thatched. Tiebeams, principals, collars. (1st floor jettied over cross-passage, but re-used timbers include 1488+ & 1563-88).	SK 387251
1610	1600 -1620	Kent	Ivy Hatch	Ightham Mote (NT)	28.124 Notm	Rebuilt first floor of West Range.	TQ 585535
1610	1602 -18 OxCal	Lon	Tower Hamlets	Tower of London	51.109 Oxf rep 2019/33	The Bloody Tower. Partition.	TQ 335805
1610 *c.*	1610 *c.*	Notts	Colston Bassett	Church	26.49 Notm	Bell frame.	SK 695338
1610	1608 /09 1609 /10	Oxf	Chastleton	Chastleton House (N.T.)	36.98 Oxf	3-storey courtyard house. Roof of long gallery in N range: arch-braced collar trusses with substantial *through-tenons* to the collars. (Most other roofs reconstructed after 1789 *qv*).	SP 248291
1610	1608 /09 1609 /10	Shrop	Myndtown	Asterton Home Farm House	38.132 Oxf	Reconstruction, including heightening of walls and inserting a first floor (in house of 1479 /80 *qv*).	SO 398911

1610	1609 /10 1610	Shrop	Shrewsbury	127 Frankwell	31.107 Oxf	Shops? *Box framed jettied close studded with mid-rails ogee braces*, 'queen posts' [queen struts?]	SJ 488128
1610	1609 /10	Sus E	Brighton	Patcham Barn	44.101 Oxf	4-bay aisled extension – arcade posts, tiebeam. Side-halved & bridled scarfs on arcade plate. In house 1, a further reconstruction phase 1621-42 (d). (For 1st phase see 1402 -11, & for phase 2 see 1550 *c.*).	TQ 302091
1610	1600 -28	Worcs	Wribbenhall	Pleasant Harbour House	38.118 DCL	*Brick* house, now part of a terrace with *hipped* end.	SO 788755
1611	1611	Ches	Tattenhall	Upper Brereton Park Farm	42,89 TAUB/03/10	Timber-framed, large rectangular panels. Gabled. Staggered tenoned purlins. [queen posts or queen struts?]	SJ 502633
1611	1598 -1623	Cor	Mousehole	Keigwin Place	40.111 Notm	Parlour wing roof.	SW 469263
1611	1598 -1623	Dev	Drewsteignton	Middle Venton Farmhouse, Venton	43.88 Notm RDR 23-2011	Ceiling inserted (into longhouse hall of 1507 -30 *qv*).	SX 174877
1611 *c*.	1611 *c*.	Dors	Sherborne	The Priory House	45.101 *DTPH/21/13*	Principal rafter truss with trenched side purlins. (Also a strut, of re-used timber, 1535-67).	ST 637169
1611	1595-1627	Hamps	Bishop's Waltham	Moysents, Bank Street	28.175 Oxf	Roof repaired with crown post to match existing (of 1363 /64 1371 /72 *qv*).	SU 556176
1611	1611	Hamps	Selborne	Gilbert White's House & the Oates Museum	35.105 Oxf	Building complex with 19 roof phases. No carpentry details given. (Roof phase 15 dated to 1725 -49.	SU 740338
1611	1610 /11	Hamps	Up Nately	Blaegrove Cottage, Blaegrove Lane	42.107 Oxf	E end – lobby entry & parlour bay. (Also see 1455 and 1568 /69).	SU 698517
1611	1611	Leic	Muston	Church of St John the Baptist	37.117 Notm	2 bell frames, 1 above the other, both jack-braced and with 3 trusses.	SK 829379
1611	1611	Lincs	Alford	Manor House	34.108 Notm	H-plan, with two-storey hall range, *gabled* wings. Originally *timber-framed*, with mud-and-stud walls and *thatched* roof. Clasped purlins.	TF 454759
1611	1595 -1627	Lon	Westminster	Westminster Abbey	36.91 Oxf	Pyx chamber inner door middle lock.	TQ 300795
1611	1593 -1628	Notts	Gotham	Gotham Manor	22.41 Notm	Side purlins, *cusped wind braces*	SK 536300
1611	1611	N'umb	Corbridge	Dilston Castle, Dilston Hall	35.93 Notm CfA 88/2003	Chapel. Cambered tiebeams with purlins and a ridge.	NY 962533
1611	1611	Oxf	Chastleton	Chastleton House	36.98 Oxf	Felling date of timber in brewhouse range (of house containing timber felled 1608 /09 1609 /10 *qv*).	SP 248291
1611	1611	Oxf	Henley-on-Thames	Countess Gardens, 88 Bell St	40.129 Oxf	Re-used rafters in 18thC house.	SU 760829
1611	1610 1610/11 1610 1611	Oxf	Mapledurham	Chazey Court	35.95 Oxf	a. *Brick* barn. Tiebeam & collar: but *struts rise to principals*. 2 tiers of *tenoned purlins*. Wind braces down to lower purlins, up to ridge. Repairs employed timber felled 1801. b. 7-bay 1½ storey upper cruck range added to house of 1609/10 1611; trenched purlins & ridge piece, wind braces. (Also see 1614 1614 /15).	SU 692752
1611	1609 /13+0	Oxf	Mapledurham	Rose Farm House	20.47 Oxf	*Hipped* roof, clasped purlins, *ridge piece*.	SU 685766
1611	1610 /11	Oxf	Oxford	Wadham College	41.108 Oxf (7)	Chapel roof. Coupled rafters with *collars*, *soulaces* plus *upper collars* and *king struts*.	SP 516065
1611	1600 -21	Som	Norton St Philip	Farleigh Hungerford Castle	33.76 MB CfA 55/2002.	Church / Chapel. Stone. Five bays with moulded tiebeams and collars. (Part of the roof was renewed 1765 -95).	ST 801577
1611	1610 /11	Surr	Newdigate	Reffolds	37.102 *NERE/17/05*	Parlour wing: *raking struts* and clasped purlins. (For main range see 1606 1607/8).	TQ 200432
1611	1607 1610 /11	Worcs	Hanbury	Mere Hall	36.96 Oxf	*Box-framed*. H-plan. Second-floor gallery with *side gables*.	SO 951618
1612	1610 -14	Hamps	Hartley Wespall	Hartley Court	41.106 Oxf	Riding stables. Brick. Mainly 'queen posts supporting side purlins', no collars.	SU 696584
1612	1612	Leics	Lount	Rose Cottage	41.98 Notm	Parlour wing with *square panels* and *straight braces*.	SK 386194
1612	1612	Shrop	Ditton Priors	Home Farm Middleton Priors	35.108 Oxf	No carpentry details.	SO 624904
1612	1612	Shrop	Plealy	Brookgate Farm	24.58 Oxf	East wing: *square framing*	SJ 424068

1612	1604 -19	Shrop	Wem	Tilley Farm, Tilley	46.96 *SYTD/44/14*	2½ bay end chimney house. Gabled. Internal trusses have dropped tiebeams. Queen struts, in-line trenched purlins. (Also re-used timbers 1480 /81)	SJ 508278
1612	1612	Staffs	Brewood	Black Ladies	30.125 Sh	Eastern Range, south roof. (Also see 1653-75, 1669, 1672)	SJ 847093
1613	1612 -13	Cor	Mousehole	Keigwin Place	40.111 Notm	Upper chamber roof.	SW 469263
1613	1600 -25	Derbs	Matlock	Dimple Farm, 15 Hurds Hollow	27.82 Notm	*Stone* barn. *Queen strut* roof trusses with double side purlins.	SK 293607
1613	1613 +	Dur	Darlington	Field House Farm, Nunnery Lane	11,22 Sh	Upper cruck with *collar* and *saddle* – see *VA* 11, 44	NZ 273148
1613	1611 -15	Hamps	Droxford	St Clair's Farm	47.93 Oxf	Timber-framed wing; 2 bays, central chimney, lobby entry. Close studding.	SU 604154
1613	1612 1613	Kent	Ivy Hatch	Laundry Cottage, Ightham Mote (NT)	- Notm AML 60/2000	Extension to older building, open at end? Raised tiebeam truss, crown post, *collar* – many timbers re-used.	TQ 585533
1613	1606 -20	Lancs	Cliviger (nr. Burnley)	Barcroft Hall	38.115 DCL	E-plan country house /mansion. Similar SW wing roof and 2-bay central range (date range 1607 -25) have king posts, principal rafters, 'joggled' [staggered?] purlins, *ridge purlins*. Felling date for timber in hall ceiling 1609 /10. (For NE Wing roof see 1540 /41).	SD 865304
1613	1610 /15+0	Leic	Long Clawson	Manor House	22.40 Notm	No roof details.	SK 722271
1613	1612 1613	Oxf	Berrick Salome	Lower Berrick Farmhouse	36.98 Oxf	*Box-framed*. 2-bay extension to building of 1550 *c*. (*qv*). Chamber open truss has knee braces on timber corbels, thin arch braces to collar, *V-struts*.	SU 619939
1613	1613	Oxf	Oxford	The Bodleian Library	50.112 Oxf	Staircase tower in SW corner of Old Schools Quadrangle. (Also an upper newel post of 1697d connected with reconstruction).	SU 515064
1613	1612 /13	Shrop	Aston Eyre	Hall Farm	29.122 Oxf	Barn. Horizontal boards in panels between studs. No roof details.	SJ 666202
1613	1613	Shrop	Bishop's Wood	Hunting Lodge, Boscobel House	47.81 Notm	Timber used in remodelling farmhouse as a hunting lodge includes post, stud, rail, wall plate	SJ 837082
1613	1613	Staffs	Checkley	Tean Hall, Upper Tean	38.111 Notm	*Box-framed*, *close studding with mid-rail*. Tiebeams, collars, principals, no queen struts: *trenched purlins*. (For wing see 1569).	SK 010395
1613	1612 /13	Suff	Horham	Church Farmhouse	37.121 Oxf	Repairs to wall framing of an older (undated) house.	TM 211727
1613	1611 – 1612 /13	Surr	Oxted	Court Farm Hse, Court Farm Lane	48.90 *RHCF/30/16*	3½ bay central chimney house. Staggered tenoned purlins in roof.	TQ 390529
1613	1612 /13	Surr	Smallfield	Smallfield Place	38.105 *SMSP/05/06*	Manorial. Rear wing of 2 bays and 3 storeys. *Queen struts*, clasped purlins, no braces. (Front range timbers felled 1615 1616 /17 *qv*).	TQ 326431
1613	1612 /13	Warks	Stratford upon Avon	Hall's Croft	30.103 Oxf (8)	Unit I. *Box-framed*. *Jettied*. *Square panels* above *close studding*.	SP 200545
1613	1613	Worcs	Dodderhill	Impney Farm	35.103 Oxf	Cellar ceiling joists. (Also 1467-1497: all re-used timbers).	SO 906767
1613	1612 -13	YksWR (YksS)	Bradfield	Hoyles Farm, Blindside Lane	25.42 Notm	Barn 2 near farmhouse. Gritstone. 3½ bays + single aisle. 4 full cruck trusses on padstones. Tiebeams, collars, single tier side purlins + ridge purlin, wind braces + purlin to aisle (LB desc). Apex type A. (Also see 1552 for barn 1).	SK 239905
1614	1614	Ches	Stockport	30a and 31 Market Place	30.119 Sh	Decoratve panelling in *stone* wing: no roof details. (Also see 1263+, 1553 /54, 1618).	SJ 897906
1614	1601 -26	Cor	Mousehole	Keigwin Place (1 & 2 Keigwin Place)	40.111 Notm	6 light [A-frame?] principal rafter trusses with collars (no tiebeams): 2 tiers of purlins, no ridge.	SW 469263
1614	1608 /09, 1614	Hamps	Abbots Worthy	6-7 Mill Lane	50.96 *SOML/27/18*	Timber-framed, small square panels, straight down-braces. 3-bay (central bay open). Hipped roof, queen struts.	SU 498325
1614	1613 /14	Heref	Tupsley	Lower House Farm	28.145 Sh	*Timber-framed*.	SO 535404
1614	1609 /10 1613 /14	Surr	Farnham	Viners Mead	40.109 *FAVM/06/08*	3½-bay (?) central chimney house orig with *½-hipped* roof. Walls have *small square panels*, unjowled posts, straight down-braces. *Queen struts*, clasped purlins, straight wind-braces.	SU 827451
1614	1613 /14	Warks	Stratford upon Avon	Hall's Croft	30.103 Oxf (9)	Unit 2. *Box-framed*. *Jettied*. *Square panels* above *close studding*. Unusual *jetties* (no dragon beams). (Also see 1653 -78).	SP 200545

1614	1611 1612 1614	Worcs	Bewdley	Hoarstone Farm	40.120 DCL	*Timber-framed*. H-plan + porch. Central range and wing roofs all have *A-frames* with clasped purlins, *diminished principals*, *interrupted collars* (for doorways), *straight wind braces*. In both cross-wings purlins are *clasped* at central truss but *tenoned* at each end. (Porch 1617 -28).	SO 793768
1615	1614 /15	Bucks	Boarstall	Boarstall Tower	30.99 Oxf	Heightening and new roof of remains of manor house (of 1312 /13 *qv*).	SP 624141
1615	1602 -27	Cor	Mousehole	Keigwin Place	40.111 Notm	Rear wing.	SW 469263
1615	1615	Cumb	Burgh by Sands	Lamonby Farm	29.108 Notm	*Longhouse*: *hearth-passage plan* + byre. Clay. Thatched. 9 cruck trusses?	NY 326592
1615	1600 -30	Derbs	Kirk Ireton	The Barley Mow	38.108 Notm	Domestic dwelling. Central truss with upper and lower *collars*. (House rebuilt 1675 - 1700 *qv*).	SK 266501
1615	1614 /15	Ess	Southminster	Sheepcotes Farm	44.99 Oxf (10)	Large timber-framed house of 4 bays + chimney bay, & with lobby entry. 2 storeys + attic. Dropped tiebeams, 'sling braces clasped by' the ends of stub tiebeams, collars.	TL 959007
1615	1597 -1632	Glouc	Aldsworth	Lodge Park	26.47 Notm	Roof replaced.	SP 146123
1615	1615	Hamps	Overton	31-35 High Street	33.93 Oxf	Attached kitchen or brewhouse: addition to house (of 1541 1541 /42 *qv*).	SU 514497
1615	1579 -90 1608 -22	Hamps	Titchfield	Great Posbrook Barn	40.127 Oxf	Barn: aisled. *Hipped* roof. 10 bays. Arcade posts yielded 2 different felling date ranges. *Raking struts* and clasped purlins.	SU 535050
1615	1599 -1631	Kent	Westwell	St Mary's Church	45.102 *TNSM/17/12*	Phase 2 of spire. (For spire phase 1 see 1535 -36, and for spire phase 3 see 1874 /75).	TQ 990474
1615	1615	Leic	Hoby	Warren Farm	39.108 Notm	Barn. *Box framed*. *Thatched*. *Queen strut* roof with 2 tiers of purlins, wind braces.	SK 671175
1615	1615	Norf	Pulham Market	Manor Farm	42.94 IT (11)	Hall and service end of tripartite house. Primary floored attic. Principals, collars, 2 tiers of tenoned purlins, wind braces. Sliding shutters 1599+.	TM 211884
1615	1614 1614 /15	Oxf	Mapledurham	Chazel Court	35.95 Oxf	*Brick* stable range of farmhouse (of 1609 /10, 1611). The stable roof has 1 tiebeam truss and 1 open truss with extended jowled posts. (Alterations with timber felled *c.*1737).	SU 692752
1615	1614 1614 /15	Shrop	Ludlow	Reader's House	37.129 Oxf	3-storey porch & roof reconstruction.	SO 512746
1615	1614 /15	Som	Dunster	'Tithe Barn'	47.74 *DUPH/09/15*	Stone barn. Secondary roof of 7 trusses with principals & collars fixed by bare-faced dovetails, 3 tiers of in-line tenoned purlins.	SS 990437
1615	1615 *c.*	Som	Templecombe	The Manor House, High Street	28.125 Notm	Kitchen wing. Curved braces from tiebeams to principal rafters: single side purlins.	ST 709220
1615	1602 -1627	Staffs	Ipstones	Whitehough	29.106 Notm	Wing. *Stone*. 3-bay wing. 2 inner trusses have *interrupted tiebeams* (and 2 collars?).	SK 984566
1615	1615	Suff	Linstead Magna	Model Farm	33.77 MB	3-bay lobby entry house with a chimney bay. Wall-plate has an *edge-halved and bridled scarf-joint*. *Floor joists set on edge*.	TM 307778
1615	1604 -25	Sus W	Crawley	Lowfield Hall, Lowfield Heath	48.100 Notm RRS 47/2016	Primary N-S range originally a 3-bay barn. 4 arch-braced tiebeam and principal trusses, raked struts, single tier of clasped side purlins	TQ 263398
1615	1615 *c.*	Notts ?	Egmanton	Kirton Road	13.49 Sh	Sample from 'purlin'. [Not otherwise identified. The only LB in this road is dated 1734].	SK 73-68-
1615	1615 *c.* +	YksWR (YksS)	Hoyland Swaine	Kidfield House	12.40 Sh	Firehood.	SE 253054
1616	1612 to 1615 /16	Bucks	Wingrave	Windmill Farm, Mill Lane	43.81 *WGWM/05/11*	3½ bay central chimney house. Gabled. Walls have straight and curved braces. Tiebeams, 3 struts, diminished principals, clasped purlins, curved wind braces.	SP 870188
1616	1615 /16	Cambs	Wimpole	St Andrew's Church	30.87 MB AML 59/98	Short false hammerbeams now under 2 central *tiebeams* of timber felled 1738-69 (*qv*) in a roof of very shallow (nearly flat) pitch over the Chicheley Chapel. [Suspect re-used timber?]	TL336510
1616	1616	Derbs	Heage (Ripley)	Crowtrees Farmhse., 56 Ripley Rd	28.128 Notm	Cruck. Arch-braced collar. *Yoke*, *ridge plate* ... Two other cruck blades in same bldg dated to 1435-60 [re-used?]	SK 374505

1616	1604 -27	Dev	Malborough	Yarde Farmhouse	41.95 Notm RDRS 103/2009	Manorial. Three tiers of *threaded purlins* plus a *threaded ridge-piece* in N-S range roof.	SX 717401
1616	1615 1616	Dors	Wimbourne Saint Giles	Riding House	46.90 MB	2 storeys, brick, ashlar dressings. Tiebeams, collars, queen struts, chamfered side purlins.	SU 031120
1616	1616 *c.*	Hamps	West Liss	Church of St Peter	44.93 Notm RDRS 40/2012	Nave roof – common rafter couples with arch-braced collars. [Apparently a 13thC roof has been substantially replaced]. (For S aisle see 1605 -1640).	SU 771287
1616	1616	Lon	Tower Hamlets	Tower of London	28.165 Oxf	White Tower: diagonal ties in SW turret. Numerous other later dates not included here.	TQ 336805
1616	1613 +5	Notts	Skegby	Old Road	15.68 Notm	House: cruck. (Also see 1603).	SK 499609
1616	1613 -18	Oxf	Chipping Norton	Chequers P.H., Goddards Lane	47.70 MB	N-S range roof – purlin. (For E-W range roof see 1444-76. A ceiling beam in rear bar dated 1772 -1804).	SP 314273
1616	1616	Oxf	Mapledurham	The Almshouses	37.126 Oxf	6 single-bay units with *queen-strut* roofs.	SU 670768
1616	1615 /16	Shrop	Wem	Oak Cottage, 13 Tilley	47.75 *SYTH/18/15*	2-bay central chimney house. Close studding and small square decorative panels. Hewn jetties. Tiebeam, queen struts to collar, 2 tiers in-line trenched purlins, V-struts.	SJ 507278
1616	1615, 1616	Shrop	Wem	Tilley Hall Barn	48.92 *SYTH/13/16*	6-bay gabled barn with small square panel walls. Queen strut roof trusses, single tier of staggered trenched purlins. (Also re-used timbers up to *c.* 1543).	SJ 507278
1616	1601 -31	Shrop	Wem	Tilley Manor	48.93 *SYTB/11/16*	Single-bay W wing has small square panels, hewn jetty, queen-strut roof. (For main range see1568 & for E. wing see 1606 /07).	SJ 506279
1617	1616 /17 1617	Berks (Oxf)	Abingdon	Unicorn House 28 East St Helen St	42.108 Oxf	Inn. 2 storeys, timber-framed, 6 bays. Dropped tiebeams, sling braces, cranked inner principals linked to interrupted ties.	SU 497962
1617	1617	Heref	Ledbury	The Market House	40.113 Notm RDR 53-2008	Open ground floor with moulded posts. Upper floor *jettied* all round, *dragon beams*. Walls - *square panels, herringbone framing*. *Gables* – tiebeam & collar, *struts*, *V-struts*. Internal trusses – tiebeam, *raked struts to principals* and from principals to collar, 2 tiers of *tenoned side purlins*.	SO 711377
1617	1601 -33	Kent	Sevenoaks	Knole (NT)	41.104 Oxf	East range, west roof.	TQ 539542
1617	1612 -22	Lincs	Lincoln	Cathedral	12.39 Fl	Replacement timbers in central tower.	SK 977718
1617	1617	Lon	Westminster	Westminster Abbey	36.91 Oxf	Alterations to raise floor of Jerusalem chamber undercroft.	TQ 300795
1617	1617	Notts	Bingham	61 Long Acre	39.108 Notm	Ceiling joists. The roof has been replaced.	SK 703398
1617	1613 /14 - 1617	Numb	Newcastle-upon-Tyne	Bessie Surtees House, Sandhill	42.93	Milbank House is one of two merchants' houses incorporated into Bessie Surtees House. Timber-framed. These date ranges are for levels 4-6 and roof. (Also see 1537. For Surtees House see 1507 and 1651).	NZ 251638
1617	1617	Shrop	Wem	Brook Cottage, 18 Tilley	47.76 *SYTE/08/15*	2½ bay 2 storey front range with lateral chimney. Walls 4 square panels high, straight barces, unjowled posts. Queen-strut roof, single tier trenched purlins, straight wind braces. Fdr of 1614-44 for rear wing is compatible with front range date. (Spine beam inserted 1664/ 65).	SJ 506279
1617	1615 *c.* & 1616 /17	Shrop	Wem	Palms Hill Cottage	49.127 *SYPH/28/17*	Small panel and large panel wall frames. 1½-storey 2-bay end chimney house. Gabled queen-strut roof, V-struts above collar, single tier of trenched purlins and straight wind-braces.	SJ 522273
1617	1569-94 1599 1604-29	Staffs (WMid)	West Bromwich	Oak House, Oak Road	42.103 Notm RDRS 34/2009	Originally a 2-bay hall flanked by wings. Primary phase timber felled in batches? Close-studded, jettied, dragon beam, jettied gables, tiebeam and collar, principals. (Various other felling dates might belong to one phase of *c.*1660 *qv*).	SO 992913
1617	1617	Suff	Alpheton	Mill Farm, Bridge Street	33.76 MB CfA 2/2002.	Undated hall with two wings. The date is for a beam in the inserted floor.	TL 879492
1617	1617	Surr	Abinger	Snowhill Cottage	38.101 *OAKS/28/06*	One bay added to W end (of cottage of 1594/5 1595).	TQ 134374

1617	1615 1616/17	Surr	Smallfield	Smallfield Place	38.105 *SMSP/05/06*	Front range, apparently built very soon after rear wing of 1612 /13 (*qv*). Rear roof slope has *tenoned purlins in line*, but front has *staggered tenoned purlins*.	TQ 326431
1617	1616 /17	Surr	Thursley	Creedhole Farm	37.106 *THCF/04/06*	3½ bay central chimney house. Walls have jowled posts, straight braces. '*3 queen struts*' per truss, clasped purlins, *straight wind braces*. [Listed in *VA* 38.105 as 1616 ?]	SU 907365
1617	1599-1635	Worcs	Clifton on Teme	Woodmanton Manor	33.116 Sh	Floor inserted (into hall of 1321 -53? *qv*)	SO 719605
1617	1604 -29	YksWR (YksN)	Markenfield	Markenfield Hall	33.113 Notm CfA 59/2002	Moated. Manorial. Gatehouse. *Stone*, *gabled*, 3 *shallow pitch tiebeam trusses* with principals (no collars); *tenoned side purlins*, no ridge-piece.	SE 295673
1618	1617 /18	Cambs	Ely	The Canonry House	23.51 Notm CfA 74/2004	Hall over undercroft. Tiebeam and collar principal trusses: lower *purlins tenoned*, upper *purlins trenched* into soffits of rafters.	TL 541802
1618	1618	Ches	Stockport	30a and 31 Market Place	30.119 Sh	Street range: no roof details. (Also see 1263+, 1553 /4, 1618).	SJ 897906
1618	1617 /18	Heref	Hereford	42 Widemarsh St	28.144 Sh AML 17/96	Replacement roof.	SO 510402
1618	1605 -30	Norf	Langley with Hardley	Langley Abbey	46.99 Notm RRS 25/2014	Former west cloister range (13thC stone walls). Roof has tiebeams, principals, lower and upper collars, 2 tiers of tenoned purlins. (For stables see 1433 -58).	TG 362028
1618	1617 /18	Norf	Tacolneston	Tacolneston Hall	42.95 IT	West wing added to house of 1543 (*qv*). Notched chamfer stops in parlour. East wing date range 1613-49 overlaps; arched collar: lower tier of staggered purlins, upper tier with 'cranked inverted arch windbraces'.	TM 138955
1618	1618	Oxf	Oxford	Jesus College	39.137 Oxf	Hall. Hammer beam roof ... 'a throwback to the medieval period ...' as also at Wadham (1610-13) and Oriel (1637-42). (Hall ceiled in 1741).	SP 515064
1618	1615, 1617 /18	Shrop	Wem	Ferndale Barn	48.92 *SYTL/08/16*	Box-framed 5-bay barn originally with small square panels; tiebeams, queen struts, single tier staggered trenched purlins, ridge purlin, straight wind braces. (Some tiebeams may be re-used cruck blades of 1457 /58 *qv*)).	SJ508277
1618	1616 /17 1617 /18	Shrop	Wem	The Hayracks, Tilley	46.96 SYTC/43/14	4-bay barn originally with small square panel walls. Tiebeams, raking queen struts, collar, king struts above collars. (Also 1700 /01 for repairs).	SJ 507278
1618	1618	Suff	Bedfield	Bedfield Hall	38.123 Oxf	Front part of west wing. (Also see 1420, 1603 /4, 1625 /6 1628).	TM 227264
1618	1595 -1640	Surr	Reigate	43 High Street	21.45 MoL (12)	*Gabled*. Stone basement, *timber-framed* above: *small square panels*. Re-erected at Weald & Downland.	TQ 252502
1618	1618	Worcs	Wribbenhall	3 Beales Corner	38.117 DCL	*Close studded*, *jettied*. 2 bays, 2 storeys and attic. (For wall paintings see *VA* 34, 61-2).	SO 788754
1618	1605 -30	YksWR (YksN)	Austwick	Cat Hole Barn, Feizor	51.137 51.88 Notm	Purlins, arguably from former cruck barn. (Other timbers dated to 1774).	SD 784677
1618	1605 -30 1606 -30	YksWR	Pontefract	3, Cornmarket	48.102 Notm RRS 74/2015	Front range roof (1605-30) has tiebeam and collar roof with 2 tiers of side purlins. Rear range roof (1606-30) has 'tiebeam and principal' roof trusses with 2 tiers of staggered side purlins.	SE 454219
1619	1615 -22	Glouc	Gloucester	26 Westgate	33.107 Notm (13) AML 43/98	Westgate Street frontage added to structure with timbers felled 1586 -7 (*qv*). The Maverdine Lane façade employed timbers felled 1615-22. *Jettied*. *Close-studed with mid-rails*. Each bay has *close-studded gables*.	SO 831187
1619	1618 /19	Ess	Coggeshall	8 East St	43.95 IT (14)	2½ bay heated jettied rear wing. In wall-plates, edge-halved and bridled scarf joints. Roof may not be primary.	TL 850225
(1619)	(1619)	Hamps	Titchfield	Market Hall	- (15)	The dendro date of 1520 + (*qv*) apparently superseded as Weald & Dnlnd Museum have published a tree-ring date of 1619 (not in VA). *Gabled*, *close-studded*, *straight down-braces*. Tiebeam and collar roof.	SZ 536057
1619	1619 *c*.	Hamps	Yateley	Monteagle House, Monteagle Lane	35.75 *YAMH/19/03*	*Staggered tenoned purlins*.	TQ 805601
1619	1618 /19+0	Leic	Donnington le Heath	The Manor House	20.40 Notm	Replacement roof: tiebeam and collar. (Also see 1287)	SK 421126
1619	1601 -37	Norf	Oxborough	Oxburgh Hall (NT)	35.87 Sh	Moated. Manorial. East range northern roof. (Also see 1748 *c.*)	TF 742012

1619	1619	Notts	Cossal	Church of St Catherine	47.84 Notm	Bell frame with queen posts and curved braces.	SK 483422
1619	1619	Oxf	Mapledurham	The Bothy	34.111 Oxf	Stone and brick. 1½ storeys. Re-used principal rafters failed to date.	SU 670768
1619	1619	Oxf	Rotherfield Greys	Greys Court (NT)	40.128 Oxf	South porch. (Also see 1443 /44 &c.)	SP 681364
1619	1618 /19	Shrop	Bishop's Castle	Old Market Hall, High Street	39.140 Oxf	3 rows of 7 posts on padstones. 1st 4 bays floored, end 2 bays open to ridge. (Some ex-situ timbers had a felling date of 1717+).	SO 324889
1619	1618 /19	Shrop	Whitton	Whitton Court	48.89 SYWC/53/16	4-bay wing with lateral chimneys. Gabled. Jettied: ground floor close-studded with midrail, 1st floor square panels with decorative framing. Roof - queen struts from tiebeams to principals	SO 578734
1619	1618 /19	Surr	Dockenfield	Boundary Road, Little Oakley	45.103 *GULO/19/13*	2½ bay end-chimney house, gabled & ½-hipped. Tiebeams, queen struts, clasped purlins, undiminished principals, straight windbraces.	SU 820416
1619	1608 -29	Worcs	Stourport on Severn	Hartlebury Castle	40.120 DCL	Saloon roof. *Tiebeam [& collar?*], *queen struts*. (Also see 1428 -47, 1469, 1678).	SO 836712
1620	1620 *c*.	Berks (Oxf)	Aston Tirrold	Tirrold House, Aston Street (formerly The Cottage)	*MPHE* AST-A 23.58	Inscribed date. Floor inserted into bay III & 2-bay range added. Smoke-hood. (For chamber block see 1282 -84 & for hall bay see 1518/ 19).	SU 556858
1620	1618 -22	Derbs	Hartshorne	Upper Hall, 10 Main Street	39.121 Notm	*Box framed*. *Queen strut* roof. *Decorative framing*.	SK 325213
1620	1619 1619 /20	Hamps	Corhampton	Franklin's Farm, Dean	40.125 Oxf	Floored hall with heated chamber over. *Queen strut* roof.	SU 570204
1620	1620	Hamps	Dogmersfield	Pilcot House	37.123 Oxf	*Box framed*. *Small panel* framing with *straight braces*. Lobby entry plan. Roof has tiebeams, *queen struts*, clasped purlins.	SU 786529
1620	1620	Hamps	Hinton Ampner	Black House Farm	32.80 Oxf	L-plan house: 1½ bay kitchen wing with back-to-back chimney and *lobby entry*: 2-bay parlour wing, prob. contemporary. *Small panel* framing, *short straight braces*.	SU 610255
1620	1619 -21	Heref	Kington	Hergest Court	28.159 Oxf	Undercroft pentice. (Also see 1267).	SO 281554
1620	1620 *c.*	Kent	Penshurst	Swaylands Barn, Workhouse Farm	32.94 Notm CfA 36/2001.	Barn. Three bays. *Timber-framed*.	TQ 534427
1620	1620	Leic	Whitwick	5-7 Market Place	47.79 Notm	Primary timbers include cruck blades. (For re-used king post see 1471-96).	SK 435160
1620	1614 -26	Norf	Aldeby	Aldeby Hall - barn	45.112 Notm	Barn? Brick, 8 bays, 2 storeys + attic. 7 tiebeam trusses. 2 tiers of side purlins.	TM 444928
1620	1620	Shrop	Ash	Ashwood	25.31 Oxf	Hall floor inserted (see 1549 1550).	SJ 586404
1620	1620 *c* ?	Staffs	Shobnall	Sinai Park	28.146 Sh	Felling date range was 1597-1640. Lower portions of Bldg C. (Also see 1494-1534, 1572-3).	SK 223232
1620	1600 -25 1620	Suff	Debenham	The Buck's Head, 27 High Street	35.94 Notm CfA 41/2003	Another phase of works (?) (on grandstand of 1578+:1605 *qv*).	TM 173632
1620	1619 -20	Worcs	Wribbenhall	Bridgewater Cottage	38.118 DCL	*Box-framed*, 2 storeys +attic, originally with 3 dormers. Walls *4 square panels high*. Internal trusses have *interrupted tiebeams*.	SO 788755
1620	1607 -32	YksWR (YksS)	Nr Sheffield	Hallfield House, Bradfield Dale	27.83 Notm	Cruck barn (of 1505 *c. qv*) also has inserted cruck blades of 1617 -10+15.	SK 234915
1621	1620 1621	Cambs	Ellington Thorpe	The Crooked Billet	39.114 *HUBI/21/07*	3½ bay *smoke bay* house with *hipped* roof.	TL 159707
1621	1617 – 1625 *c.*	Cambs	Sutton-in-the-Isle	St Andrew's Church	28.139 Sh	Bellframe	TL 448790
1621	1620/21	Cor	Lostwithiel	Old Duchy Palace	41.90 DCL RDRS 1/2010	*Stone*. No roof details.	SX 104597
1621	1619 /20 1621	Shrop	Ludlow	Lane's House, 56 Old St	37.128 Oxf	*Stone* to ground floor, 2 *box-framed* storeys above. 2 'dormer gables'. *Close studding*, *herringbone work*, *diamond strutting*.	SO 513745
1622	1621 /22	Derbs	Ockbrook	Church Farmhouse, Church St	40.112 Notm	Bldg A – *square panel* framing. (Also see 1672).	SK 423357
1622	1621 /22	Hamps	Steep	Tankerdale Farm	29.119 Oxf	Farmhouse. *Box-framed*. *Close studding*. *Lobby entry*, rear outshot encloses a stair tower. Internal rear jetty. *Queen struts*, clasped purlins.	SU 766258

1622	1621 /22	Leic	Appleby Magna	The Moat House	39.108 Notm	Tiebeams and bridging beam. (A ceiling joist dated 1509 -34).	SK 316098
1622	1609 -34	Leic	Hallaton	11, Hunt's Lane	51.128 Notm (16)	Front range did not date. Rear wing, 2 storeys, cruck, gabled, originally open to roof.	SP 786966
1622	1622	Lon	Tottenham	The Priory, Church Lane	31.86 MB	Prob. built for Joseph Fenton *c.*1620. Remnants of primary roof timbers suggested an earlier date which has not been supported by the tree-ring results.	TQ 333908
1622	1609 -34 1424+	Notts	Norwell	Scott's Cottage, Bathley Lane	42.96 Notts RDRS 70/2010	Truss 2 tiebeam indicates reconstruction. (See 1412 -37).	SK 769615
1622	1622	Shrop	Shrewsbury	Vaughan's Mansion, Market Square	44.95 Notm (17)	Cross-wing roof – tiebeam, collars, principals, 2 tiers of trenched side purlins. (For hammer beam roof see 1469).	SJ 490124
1622	1603 -41	Staffs	Middle Mayfield	Old Farmhouse	37.114 Notm	3-room *lobby entry* plan. Vertical studs between tiebeam & collar. 2 tiers of *trenched purlins* (but roof partly rebuilt). (Re-used principals dated to 1558).	SK 145445
1622	1620 /21 & 1621 /22	Suff	Dallinghoo	Pound Corner House, Pound Lane	44.88 *IPPC/20/12*	4½ bay central chimney house with lobby entry. 2½ storeys. Large rectangular panels with straight braces. Jowled posts. Tiebeam and collar, principals, straight, clasped purlins.	TM 268543
1622	1622	Surr	Worplesdon	Frosbury Farmhouse	34.96 *FRWO/28/02*	Timbers belonging to floor inserted into hall range of *c.*1550 (which has wing with timbers felled *c.* 1552? *qv*).	SU 969519
1622	1621 /22 & 1622	Warks	Stratford upon Avon	Falcon Inn, Chapel Street	49.140 Oxf	Chapel Street range. Close-studded. Originally double-jettied. (Also 'later work' of 1660 /61).	SP 200547
1622	1604 -1640	Wilts	Clarendon	The Old Mansion	30.126 Sh	Transverse floor beams. (Also see 1638 -80).	SU 195285
1622	1609 -34	Wilts	Clarendon	Queen Manor Farm	30.125 Sh	Granary.	SU 177312
1622	1622	YksNR (YksN)	Helmsley	Canons Garth	Notm 46.101 RRS 39/2014 (18) (19)	W wing roof – tiebeams, principals, king struts? [apparently not crown-posts as in VA], raking struts. Also W wing fireplace 1629. (For vicar's open hall with base cruck and crown post roof see 1283. For first floor inserted into open hall see 1622 -39. For SW wing roof see 1551 -71).	SE 612839
1623	1623	Berks	Newbury	102 -3 Bartholomew Street	51.116 *RGBC/02/19*	Timber-framed, small rectangular panels, gunstock jowls on posts. Gabled roof, queen struts, clasped purlins.	SU 469668
1623 +	1623 +	Berks	Windsor	Windsor Castle	26.60	'…later repairs…'	SU 970770
1623	1600 -45	Bucks	Fenny Stratford	The Chantry House	24.48 MB	No roof details.	SP 638165
1623	1620 -25	Cambs	Ely	The Queen's Hall, Cathedral Close	- Notm CfA 74/2004	Original roof was 'flat'. This replacement pitched roof has a single tier of side purlins, *straight wind-braces*.	TL 540801
1623	1623	Ches (GrMan)	Stockport	Church of St Mary, Churchgate	46.97 Notm RRS 56/2014	Vestry roof. Slightly cambered tiebeams, raking struts to principals. Single tier of side purlins plus ridge purlin.	SJ 897905
1623	1620 -25	Dev	Churchstow	Leigh Barton	31.120 Sh (20)	Gatehouse. This date is for North range roof, with 7 roof trusses: some *principals with curved feet*, others are *jointed to short posts* in the wall. A ceiling beam dated 1615 -51. (Also see 1494 -1521 and 1783 /84).	SX 723468
1623	1612 -33	Dev	Drewsteignton	Drascombe Barton	50.101 Notm	Cider house. Cob on rubble footings. ½-hipped roof. A-frame trusses, 2 tiers trenched side purlins. (For house, first see 1620-44).	SX 701920
1623	1622 /23	Ess	Cressing Temple	Cressing Granary	28.141 Sh	Felling date corresponds to date on carved plank.	TL 799186
1623	1621 /22 1623	Hamps	Titchfield	St Margaret's Priory	31.104 Oxf	No roof details.	SU 534063
1623	1605 -40	Hamps	West Liss	Church of St Peter	44.93 Notm RDRS 40/2012	South aisle roof. Common rafter couples with arch-braced collars, but some rafters have empty mortices. (For Nave roof see 1616 *c.*).	SU 771287
1623	1623	Lancs	Bury	Deardon Fold Farmhouse	30.119 Sh AML 66/98.	Beam over cellar in house (of 1488 *qv*).	SD 758103
1623	1607 -39	Oxf	Nettlebed	18 Crocker End	45.96 Oxf	Floor inserted (into wing 1440 /41 *qv*). (Also see 1413 /14 for hall).	SU 709868
1623	1613 -33	Som	Wookey	St Matthew's Church	43.99 Notm	Bellframe.	ST 518457
1623	1622 /23	Surr	Abinger	Volvens	37.100 *ABVO/02/05*	3½ bay 2½ storey central chimney house. Main roof has *dropped tiebeams* and clasped purlins. *Gable* on front elevation and 2 rear wings have unjowled posts, *tenoned purlins*.	TQ 135405

1623	1623	Surr	Hascombe	Markwick Farm, Loxhill	31.111 Oxf	Barn. *Timber-framed*.	SU 995382
1623	1623	Wilts	Wilsford	The Malthouse	49.141 Oxf	Timbers in wing W of earlier cruck range. (See 1410 for primary cruck-framed phase).	SU 097572
1624	1624	Bucks	Little Missenden	The Manor House	36.89 Oxf	S wing. (Also see 1545 1546).	SU 922989
1624	1624	Ess	Burnham-on-Crouch	Pinner's Farmhouse	51.139 Oxf (21)	4 bays, 1½ storeys. Corner post, 'needle beam'.	TQ 937972
1624	1624	Ess	Maldon	Beeleigh Abbey	33.116 Sh	'*Timber-framed* extension' on site of lost reredorter. (Also see 1513 and 1511 -39).	TL 840077
1624	1614 -33	Kent	Ivy Hatch	Ightham Mote (NT)	30.90 Notm	Frieze panels from drawing room.	TQ 585535
1624	1624 *c*.	Leic	Loughborough	Warner's Lane / Church Gate	15.66 Notm	Added wing. (Also see 1348).	SK 538200
1624	1624	Norf	New Buckenham	Pinchpot, Chapel Street	36.83 IT	*Lobby-entrance* house. *Serpentine braces* face down street. *Diminished haunch soffit tenons*, straight bracing, *joists set on edge*. No roof details.	TM 086904
1624	1624	Notts	Screveton	St Wilfred's Church	27.79 Notm and 47.86 Notm	Boards removed from roof of tower (VA 27.19). Jack-braced bell frame with timber felled 1622 and 1624 (VA 47.86).	SK 729434
1624	1623 /24 & 1624	Oxf	Wheatley	The Manor House	46.112 Oxf	Main range, originally same date as wing, was rebuilt in 1624. (For wing see 1600)	SP 594058
1624	1623 /24+0	Staffs	Stoke on Trent	Ford Green Hall, Smallthorne (museum)	23.54 Notm	2½ storeyed hall and wings plus storeyed porch with side entrance. *Jettied* 1st floor and gables. *Close studding* with 2 rails, *small square panels* with *lozenge* and *baluster* decoration. Tiebeam and collar, queen struts.	SJ 888509
1624	1624	YksWR (YksS)	Brampton-en-le-Morthen	Old Hall Farm	11,23 Sh	'Collar-rafter roof'	SK 486884
1624	1602 -46	YksWR (YksS)	Eckington	Old Kent House, Ridgeway	21.44 Sh	No roof details. (Also see 1646 -47).	SK 403818
1625	1625	Berks	Newbury	Cloth Hall (Newbury Museum)	40.118 DCL	*Timber-framed*, with 6 bays, 2 storeys.	SU 472671
1625	1619 & 1625	Ches	Middlewich	The White Bear, Wheelock St	43.81 *CWWB/26/11*	Fragments of 4-bay timber-framed building. Tiebeam, raking struts, principals.	SJ 702662
1625	1615 -35	Ches	Risley	Old Abbey Farmhouse	30.115 Sh (22)	Moated. Timbers of this date recovered from farmhouse, now demolished. (Also see 1268 after and 1534 -1572).	SJ 662935
1625	1612 -37	Cumb	Strickland Roger	Burneside Hall	51.124 Notm RRS 51/2019	Wing trusses 3 & 4: tiebeams, principals, half-lapped cranked collars, side purlins. (For main hall see 1579 -1604, 1595 -1620. For gatehouse roof trusses see 1584-1609).	SD 509959
1625	1625	Derbs	Barlow	Woodseats Hall Farm, Johnnygate Lane	27.81 Notm	Blades in S end truss of cruck barn (built 1535 *qv*).	SK 316754
1625	1625	Dev	Bradninch	Lower Coombe Farmhouse	34.110 Oxf	Plank and muntin screen.	SS 987036
1625	1624 /25 1625	Dev	Farringdon	Upham House, Upham Lane	50, 102 Notm	Cob and sandstone. Main range has 4 side-pegged jointed cruck trusses with straight collars, 2 tiers trenched side purlins + ridge purlin. Elm truss in rear block.	SY 020907
1625	1615 -35	Heref	Much Dewchurch	The Mynde	31.115 UoW AML 53/99.	Date range is for North Wing: first-floor structure 1619.	SO 470295
1625	1625	Leic	Hinkley	5 -7 Regent Street	39.108 Notm	2 storeys, originally 5 bays? *Box framed*. Tiebeam and collar trusses. Primary timbers 1625. (Inserted timbers dated 1662, & a re-used timber dated 1510 -35).	SP 425938
1625	1625	Leic	Saltby	Saltby Church	26.48 Notm	Bell frame.	SK 851266
1625	1623 /24 1624 /25	Oxf	Mapledurham	The Old Estate Yard	36.99 Oxf	*Box-framed* (now brick), originally with lath-and-plaster external walls. 1½ storeys, orig. 4-bay roof with central *tiebeam truss* & 2 intermediate arch-braced collar trusses. Purlins clasped at gables but *double tenons* at internal trusses.	SU 670767
1625	1625	Oxf	Oxford	New College – kitchen & hall range	45.124 Oxf	Timber in inserted buttery ceiling at N end of bay 2. (For kitchen roof see 1383, for pantry ceiling see 1448-49, also see 1533 & 1724 /25).	SP 517064
1625	1625 +	Shrop	Bucknell	(Craven Arms) Barn	13.48 LP	Date cited here is from VA18.56. No roof details.	SO 36-74-

1625	1624 /25	Shrop	Oswestry	Raven Cottage 2 Lower Brook St	42.90 OSRC/08/10	2½ bays, central chimney. Square and rectangular panels, mid-rails, straight braces, lamb's tongue stops. Tiebeam and collar, principals, triple struts.	SJ 288292
1625	1625	Shrop	Whitchurch	The Raven, 17-23 Watergate	28.168 Oxf	*Close studding with mid-rail*. Tiebeam and collar.	SJ 542414
1625	1614 & 1625	Warks	Alcester	War Memorial Town Hall	51.132 Notm	Doc. date *c.*1618, but 1 tiebeam inscribed 1641 & tree-ring dates for roof are 1614 & 1625. Many alterations and redundant mortices. (For first-floor frame see 1712-37).	SP 090575
1625	1625	Worcs	Bransford	Gilberts Farm	35.103 Oxf	Single bay addition to (undated cruck-framed building). *Large panels*. Tiebeam 'queen posts'[queen struts?], 'upper diagonal bracing'	SO 801519
1625	1625	YksWR (YksS)	Halifax	Raw End Barn, Raw End Rd., Warley	46.102 Notm	Aisled, timber-framed barn. 2 king-post trusses.	SE 384143
1626	1626	Bucks	Olney	Church of St Peter and St Paul	40.122 Oxf	Bellframe	SP 889509
1626	1624 -27 1625 -27	Dev	Drewsteignton	Natton Hall	50.102 Notm	Shippon. Granite rubblestone and cob. Originally 3-room cross passage plan with 4-bay shippon. 3 A-frame trusses, 2 tiers trenched and threaded purlins	SX 701917
1626	1623 -28 *c*.	Dur	West Auckland	The Old Hall	41.91 Sh RDR 75/2009	Farmhouse. West end of roof has high collars, and two tiers of *trenched purlins*. (Also see 1671 *c*.)	NZ 180263
1626	1625 1626	Oxf	Mapledurham	The Watermill	41.108 Oxf	Another phase of rebuilding of the water-mill.	SU 669767
1626	1624 /27+0	Oxf	Nuffield	Upper House Farm House	20.47	No roof details.	SU 664865
1626	1626	Staffs	Horton	Horton Hall	Notm (23)	Large stone C-plan country house. W. wing roof has tiebeams, principals, raking & vertical struts to collars, V-struts.	SJ 940574
1626	1625 /26	Sus W	Heyshott	Hoyle Farm	47.74 *GUHF/22/15*	S wing roof. 4 tiebeam and collar trusses, in-line tenoned purlins, straight wind braces. (For hall range see 1542 /43, for smoke bay see1584 /85, and for W range roof see 1692 /93).	SU 911188
1627	1627	Beds	Pulloxhill	Rectory Farmhouse, Church Road	48.84 *MKRF/57/16*	2-bay 2½ storey gabled rear wing with central chimney. [Tiebeam and collar?], queen-struts, wind braces. For main range see 1568.	TL 061338
1627	1626 /27	Cambs	Soham	St Andrew's Church	39.112 MB	Nave roof - replacement 'wall post'. (Also see 1477 -1509).	TL 593732
1627	1614 -39	Derbs	Bretby	Bretby Hall	33.103 Notm (24)	The third hall was built 1812-13 by James Wyatt, but portions of the 17thC house were retained. Roof timbers of the north range were dated 1619-44: the roof of the wing at the E end of the N range yielded dates of 1614-39 and 1618-19. (Also see 1637 -62, 1718 and 1800 -1805).	SK 300225
1627	1604 -49	Hamps	Beaulieu	Beaulieu Abbey	23.45 Sh	Domus. 2nd phase. (Also see 1399+).	SU 399026
1627	1627 **i**	Oxf	Oxford	Lincoln College Chapel	50.89 Swan 029	Panelled, canted roof in chapel made late use of lap joints and half-dovetails. *1629-31 (doc. - Pevsner)*. (Also see 1626-29 in VA48.117).	SP 514063
1627	1627	Shrop	Ditton Priors	The Hall Farm	35.107 Oxf	No carpentry details.	SO 605888
1627	1627	Shrop	Wistanstow	Holy Tinity Church	28.161 Oxf	Also see 1200-1221. (Repairs to 13thC roof).	SO 433856
1627	1626 /27	Surr	Thursley	Ridgeway Farm	38.105 *THRI/02/06*	Kitchen wing added to hall range (of 1436 *c. qv*).	SU 891385
1627	1627	Warks	Astley	Astley Castle	28.130 Notm	North Wing. Dendro coincides with 1627 datestone found on site. Lower walls *stone*, upper *jettied close studded* but now encased behind 19thC brickwork. Fire in 1978.	SP 311894
1627	1627 *c.*	YksNR (YksN)	Bellerby	Old Hall, Main Street	48.88 *DLOH/34/16*	3-storey L-plan central chimney house with rubble walls, ashlar dressings, slate roof. Storeyed porch. Tiebeam and collar trusses.	SE 115929
1627	1627	YksWR (YksS)	Dodworth	Lane Head Farm	37.107 Sh	Demolished. Wall frame of widely-spaced posts with slightly *curved braces up to a wall-plate* with *bridled and halved scarf joints*.	SE 316061
1627	1627 +	YksWR (YksS)	Stannington, Sheffield	Whitehouse Farm	14.61 Sh	?	?
1628	1628	Berks	Winkfield	St Mary's Church	38.106 Notm	'Flat' roof on brick tower of 1629. (Adapted 1780 -1805 *qv*).	SU 904724

1628	1628	Oxf	Witney	Manor House, Cogges Manor Farm	27.95 Oxf (25)	Addition of first floor and attic into hall range. (Also see 1554).	SP 363096
1628	1625 /26 1628	Suff	Bedfield	Bedfield Hall	38.123 Oxf	Hall roof and east wing. (Also see 1420, 1603 /4, 1618).	TM 227264
1629	1619 -39	Derbs	Alfreton	St Martin's Church	- Notm RDR 45/2008	Belfry floor (also with timber felled 1575 -95).	SK 407559
1629	1628 1628 /29	Glouc	Blakeney	Swan House	40.122 Oxf	Originally fully *timber-framed*. Highly unconventional roof.	SO 672070
1629	1628 /29	Hamps	Ashley	Ashley Cottage	30.106 Oxf	Date of late insertion of upper floor into a late open hall: (also see 1567 1567/8).	SU 383311
1629	1617 -40	Norf	Tacolneston	St Mary's Farm	42.95 IT	Parlour wing. 2 storeys + attic. Single tier of staggered tenoned purlins, inverted arch wind-bracing.	TM 149941
1629	1622 -35	Oxf	Kelmscott	Kelmscott Manor	51.131 Notm	North barn. Limestone rubble, 3 bays. Tiebeams, collars, principals, raking struts, 2 tiers of side purlins.	SU 251989
1629	1626 to 1629	Oxf	Oxford	Lincoln College, Turl Street	48.117 Oxf	Chapel range roof (over boarded ceiling) made late use of lap joints and half-dovetails.	SP 514062
1629	1627 /28 1628 /29	Shrop	Clungunford	Clungunford Farm	33.97 Oxf	Hall range. *Interrupted tiebeams*. (For wing see 1591 /92).	SO 397787
1629	1628 /29	Shrop	Whittington	Whittington Castle	35.106 Oxf	1½ storey *box-framed* cottage to rear of N tower.	SJ 325312
1630	1630 *c.*	Derbs	Shardlow	Moor Farm Cottage (S), London Rd	25.36 Notm	18thC brick cottage with re-used timbers in roof.	SK 428306
1630	1630 +	Lancs	[nr. Warrington?]	Bewsey Hall	13.48 LP	Date cited is from VA18.56. Demolished *c.*1950.	SJ 586896
1630	1629 /30	Oxf	Oxford	Magdalen College	40.128 Oxf	Great Tower. Ex-situ timbers belonging to a repair phase.	SP 521061
1630	1630	Oxf	Wheatley	Rectory Farmhouse	38.131 Oxf	*Stone*. 2½ storey, with stair tower on one side. Main range roof of arch-braced principal trusses. 2 tiers of *tenoned purlins* support *tenoned common rafters*.	SU 922989
1630	1629 1630	Shrop	All Stretton	Old Hall Farm	27.102 Oxf	Lobby entry range. Tiebeam and collar, *queen struts*. Also see 1565.	SO 461953
1630	1630	Staffs	Wetton	St Margaret's Church	35.94 Notm CfA 22/2003	Bell frame in west tower (of 1492 -1517 *qv*. The sub-structure beneath the bellframe included timber felled 1590).	SK 108553
1630	1623-36 *c.*	Suff	Mettingham	All Saints' Church	41.85 MB	Roof over round tower.	TM 363900
1630	1629 /30	Suss E	East Grinstead	4 High Street	32.85 Oxf	Inserted attic floor over hall (of 1451 /52 *qv*).	TQ 395379
1631	1631	Berks (Oxf)	South Moreton	Manor House, Paper Mill Lane	50.113 Oxf	Reconstruction of N bay of E wing. (For east wing crown-post roof & primary first floor see 1314 /15, for base cruck hall range see 1397 /98).	SU 562882
1631	1629 -30 ? to 1631	Midx (GrLon)	Richmond	The Dutch House, Kew Palace	48.113 Oxf	Earliest Flemish bond brickwork in England? Roofs – 3 parallel structures, all with tenoned side purlins.	TQ 184774
1631	1630 -31	Warks	Baddesley Clinton	Baddesley Clinton (NT)	33.86 Oxf (26)	Great parlour roof. Double arch-braced common rafter collars. (Also see 1641 /42 etc).	SP 200715
1631	1630 /31 1631	Warks	Stratford upon Avon	Hall's Croft	30.103 Oxf (27)	Kitchen / service range. *Box-framed*. *Square framing 3 panels high*. *Short straight braces* to *tiebeam & collar*, *queen struts*, principals, *trenched purlins*, *ridge purlin*.	SP 200545
1631	1622 -39	YksNR (YksN)	Helmsley	Canons Garth	Notm 46.101 RRS 39/2014 (28) (29)	First floor inserted into open hall. Floor also retains timber dated 1546 -71. (For vicar's open hall with base cruck and crown post roof see 1283. For SW wing roof see 1551 -71, and for W wing roof see 1622).	SE 612839
1632	1613 -51	Ches	Stockport	30A-31 Market Place	28.143 Sh	Not a clear result.	SJ 897906
1632	1632	Derbs	Walton	Spring House Farm	26.53 Notm	4-bay cruck barn with type A apex: projecting tiebeam ends carry wall-plates: intermediate and upper *collars*: '*lap-jointed' purlins*.	SK 351695
1632	1620 -44	Dev	Drewsteignton	Drascombe Barton	50.101 Notm (30)	North part of house – cob. Originally 3-room & cross passage (?) but now with double cross passage. A-frame trusses, principals halved to short vertical posts. 2 tiers threaded purlins + ridge purlin. (For inserted floor see 1658-94 (?), for south part see 1694-7. For cider house see 1612 -33).	SX 701920
1632	1632 *c.*	Glouc	Hewelsfield and Brockweir	Gen Wye	51.118 *NP/GW/35/19*	Stone. 4-bay lateral chimney house. Tiebeam and collar trusses, 2 tiers trenched side purlins.	SO 539011

1632	1632	Hamps	Sherborne St John	The Vyne (NT)	28.176 Oxf	Summer-house.	SU 633563
1632	1632	Lancs	Pilling	Field House, Field House Lane	41.97 Notm	*Thatched*. 2 cruck trusses with type 2 apexes. *Straight wind braces* up to a single tier of side purlins.	SD 411483
1632	1632 +	Lincs	South Kesteven	Church of All Saints, Fenton	37.113 Notm	Nave roof.	SK 878506
1632	1632	Notts	Sutton-in-Ashfield	Teversal Manor	34.108 Notm CfA 40/2003	Outbuildings. Stone. Tiebeam and collar trusses. Two tiers of side purlins. *Straight wind-braces*.	SK 483628
1632	1632	Notts	Normanton-on-Stour	Church of St James	47.86 Notm	Jack-braced bell frame. (Bells cast 1634-35).	SK 518229
1632	1619 -44	Notts	Wellbeck	Wellbeck Abbey	35.93 Notm CfA 9/2004.	Riding House. Remodelled in mid 18thC? Console brackets support posts against walls, *curved braces* up to hammer beams, vase- shaped bosses on passing hammer-posts. *Curved braces up to collars*, *king struts* and *curved struts*.	SK 564742
1632	1631 & 1631 /32	Oxf	Oxford	Christ Church, Priory House	46.110 Oxf (31)	Joists, beams and principal rafter in Priory House south wing. A principal rafter in S range roof 1636. (For re-used timbers in east cloister see1245 and for south end of east cloister see 1490. For chapter house roof see 1259 -63).	SP 515059
1631	1630, 1631, 1632	Oxf	Oxford	St John's College, Canterbury Quad.	50.113 Oxf	Floor joists at N end of Laudian Library 1631d. Staircase C3 at W end of Old Library 1630, 1631 … 1632.	SP 513066
1632	1615 -49	Shrop	Shrewsbury	The Old Mansion, St Mary's St	27.93 Oxf	Later phase of bldg (of 1366 *qv*).	SJ 493126
1632	1632 *c*.	Som	Chard	Manor Court House, Fore Street	35.94 Notm CfA 27/2004	First-floor courtroom. Roof includes re-used purlins felled 1528 -53 but principal rafters and *collars* dated to *c.* 1632. Decorated plaster *barrel-vaulted ceiling*.	ST 323087
1632	1632 *c*.	Som	North Petherton	Parker's Field	43.92 Notm	Main range roof has 4 with tiebeam and collar trusses, principals, 2 tiers of side purlins. (For S range roof see 1651-76).	ST 298331
1632	1631 1631 /32	Surr	Leatherhead	Rowhurst	37.102 *LERO/33/05*	2-bay *brick* front range of 2½ storeys. In-line *tenoned purlins* (*and tenoned rafters?*) No wind braces. Rear wing built of timber felled 1345 /46 *qv*).	TQ 159585
1632	1632	Surr	Westcott	Stowe Maries, Balchins Lane	35.76 *WESM/23/03*	Granary or detached kitchen? 2 storeys, 2 bays. Stands in front of jettied building (of 1571 /72 *qv*).	TQ 136488
1633	1632 /33	Berks	Newbury	Weavers Cottages, 1 & 2 West Mills	49.121 *RGWC/24/17*	No. 1 – a 2½ bay central chimney house with jowled posts, small square panel wall framing with down-braces & a tiebeam, collar and queen-strut roof. No. 2, plausibly industrial, has unjowled posts, a queen-strut roof with diminished principals, clasped purlins & straight wind-braces.	SU 468670
1633	1633	Derbs	Walton	Hipper Hall, Holymoor Rd, Holymoorside	25.41 Notm	S portion of collapsed barn had pair of crucks, Apex A.	SK 339695
1633	1631 1632 /33	Hamps	Petersfield	Goodyers, The Spain	31.104 Oxf	Courtyard House: east range. (Also see 1636 1637 & 1641 /42).	SU 745241
1633	1623 -42	Kent	Great Chart	Godington Park	39.107 Notm	Floor joists in S range. (Also see 1396 -1416).	TQ 980430
1633	1630 -35	Leics	Great Easton	Brookside House, Brook Lane	43.90 Notm	3-bay lobby entry house of 2 storeys + attic. Roof rebuilt but the original had principals, two collars, 'through purlins' [?]	SP 846929
1633	1633	Notts	Carlton-in-Lindrick	Church of St John the Evangelist	47.84 Notm	Double jack-braced bell frame. Incised date 1634.	SK 588839
1633	1633 +0	Notts	Langford	The Manor House	20.40 Notm	Also 1637-14+20. Roof with principals.	SK 820589
1633	1621 -44	Rut	Oakham	Oakham Castle, Castle Lane	48.99 Notm (32)	Aisled open hall. This date range is for present roof – 5 king post trusses with collars and angled struts. (There are also re-used timbers of 1568 -93. For primary roof timbers see1160 -85).	SK 861089
1633	1633	Shrop	Upper Millichope	Forester's Lodge	26.70 Oxf	Ground-floor ceiling joists in older stone building.	SO 521894
1633	1632 /33	Worcs	Wribbenhall	The Dog Wheel, 6 Kidderminster Rd	38.118 DCL	2 bays, 3 storeys, *box framed*, *jettied*. (Rear range added 1647 -62 *qv*).	SO 788754
1633	1633	Worcs	Wribbenhall	Malthouse Row, Westbourne St	38.118 DCL	Malthouse. 4 bay 2 storey *box framed*. Walls *4 square panels high*, *long down-braces*. Interrupted tiebeams. Cargo or merchant's marks.	SO 789753

1633	1625 -41	YksWR (YksN)	Ripon	St Agnes Lodge, High Saint Agnesgate	38.115 DCL	E-W range of 5 cruck trusses. There is also a king-post range of 1542 -73 (*qv*).	SE 315710
1633	1632 -33	YksWR (YksS)	Bradfield	Fair Flats Farm, Kirk Edge Road	25.42 Notm	'Post and truss' barn.	SK 279917
1633	1617-49	YksWR (YksW)	Bradford	Old Manor House, Rosebery Road' Manningham	41.90 DCL	*Stone* hall, and wing with king post truss.	SE 150347
1634	1634	Dors	Wimbourne Minster	Priest's House Museum, 23-7 High St	26.61	Tiebeam and collar trusses, double *tenoned purlins*.	SZ 010000
1634	1633 -34	Ess	Cressing	New House Farm	28.141 Sh	Clasped purlins.	TL 800196
1634	1634	Leic	Welham	Church of St Andrew	37.118 Notm	Jack-braced bell frame with 3 trusses.	SP 477293
1634	1634 *c.*	Lincs	Barholm	Barholm Old Hall	51.128 Notm RRS 78/2019	Dovecote. Stone walls, 2 timber lanterns.. Single tier of purlins, wind-braces. However, also note *cal* 1444 -57 obtained from common rafters. (For hall see 1484, for wing see1509-34. For barn see 1730).	TF 088106
1634	1611 -56	Lon	Bishopgate	St Ethelberger's Church	28.143 Sh	Remains of belfry from bombed church.	TQ 332814
1634	1631 /32 1634	Lon	Greenwich	The Queen's House	47.89 MB DM	Inigo Jones. 1st-floor frames installed 1633 -35. Hall roof replaced above the tiebeams, which have long tabled scarf joints, the 2 halves locked by an extended tenon; wrought iron bands. Pine 'dust cover' boards of 1631 -32	TQ 387777
1634	1633 /34 1634	Midx (Lon)	Richmond	The Chapel Royal Hampton Court	38.122 Oxf	Ceiling and roof of Ante-chapel by Inigo Jones. Tiebeams, king posts, raking struts to principal rafters.	TQ 158685
1634	1634	Notts	Misterton	Ravens Farm, 8 Church Street	37.114 Notm CfA 73/2002	A late date for the main range roof with *coupled rafters* and *lap-jointed collars*; clasped purlins. Re-used (?) timber of 1482 in W wing.	SK 763948
1634	1626 -41	Som	Barrow Gurney	The Tythe Barn	39.134 Oxf	Barn, now a house. *Stone*. Pantiles. *Gabled*. Tiebeam & collar trusses, 'through-purlin'.	ST 514684
1634	1633 /34	Som	South Stoke	Packhorse Inn, Old School Inn	48.114 Oxf	Stone. 3-room plan with basement + 2½ storeys. First floor and roof oak and elm. No roof details. [Also basement ceiling 1618d – stock-piled timber?]	ST 747612
1634	1634	Suff	Thorndon	Hestley Hall	42.106 Oxf	E roof of S wing. (Also see 1539 /40).	TM 145681
1634	1633 /34	Surr	Ockham	Bridgefoot Farmhouse	39.115 *RIBB/20/07*	This date is for kitchen bay.	TQ 069566
1634	1634	YksWR (YksN)	Bank Newton	Newton Hall	39.131 IT	Barn. 5 bays with broad aisles. *Arch-braced aisle ties*. Straight braces [struts?] from aisle ties to aisle principals, which carry 3 tiers of purlins. In the nave, *arch-braced tiebeams*, king posts, *raking struts* from tiebeams to principals, 2 tiers of purlins + a *ridge purlin*.	SD 909531
1634	1634	YksWR (YksS)	Wakefield	89 Station Road, Ryhill	46.102 Notm	Barn. 4 primary timber-framed bays. Jowled posts, tiebeams, principals, 2 tiers of side purlins + ridge piece.	SE 384143
1635	1622 -47	Derbs	Doe Lea Nr. Chesterfield	Hardwick Old Hall – East Lodge (NT / EH)	33.103 Notm (33) AML 18/2000	*Shallow-pitched*, *hipped* king post roof. Date of1625 was obtained from stair treads in west lodge.	SK 462637
1635	1635 *c.*	Derbs	Sutton Scarsdale	Sutton Scarsdale Manor	28.124 Notm	Barn. Single side purlins.	SK 444687
1635	1633 -40 & 1622 -47	Glouc	West Dean	The Old Palace, High St., Bream	49.123 GLOP/19/17	Timbers in cross-wing 1633 -40 and in north range 1622-47 consistent with date of 1637 carved on fireplace. Tiebeam and collar roof trusses, trenched purlins, ridge purlins. (Also see 1465 /66).	SO 602055
1635	1634 1635	Hamps	Chilbolton	St Michael's Cottage	38.126 Oxf	Front range added to a house (of 1548 *qv*).	SU 392398
1635	1630 -40	Leic	Staunton Harold	Hilltop Farm	39.129 Notm	No roof details.	SK 385208
1635	1635	Staffs	Branston	Sinai Park	39.108 Notm	Barn (now dwellings). Posts, wall plate and tiebeams dated 1635. (Also see 1499.	SK 221230

1635	1635	YksWR	Morley	Howley Hall Farm	45.114 Notm	Cottage, 5 bays. Tiebeams, principals, king posts, struts, braces up to ridge-piece: single tier of trenched side purlins. Also 'mistal' (byre), same date, 4 bays, similar roof. (For cartshed see 1423, for barn see 1462-87).	SE253255
1635	1624 -43, 1633 1635	Yks WR (Cumb)	Garsdale	Dandra Garth	46.97 Notm RRS 22/2014	(Transferred to Cumbria 1974). Plank and muntin screens, first-floor and attic floor frames. (For main range roof see 1565-90).	SD 753897
1636	1623 -48	Cor	Egloskerry	Treludick House	39.120 Notm RDR 63/2007	5 roofs contain timbers felled between 1626 and 1647. Crudely-carpentered *A-frames* with *lapped collars* and apexes.	SX 254881
1636	1636	Ess	Coggeshall	16 East St	43.96 IT (34)	Originally part of an H-plan house with Nos. 14 & 18. Single bay jettied replacement of former hall. Evidence of 6 light transom window + frieze lights. 2 tiers of tenoned side purlins. (For parlour wing see 18 East St, 1361-93: for low end wing see 14 East St, 1435).	TL850225
1636	1622 -49	Heref	Abbey Dore	Dore Abbey (St Mary's Church)	30.120 Sh	John Abel restoration of 1633. (Also see1205 -38, 1575 -1615).	SO 387304
1636	1620-52	Kent	Westerham	Quebec House, Quebec Square (NT)	41.84 MB	Staircase – newel posts.	TQ 449541
1636	1636 +	Leic	Aston Flamville	Church of St Peter	37.116 Notm	Bells hang between 2 re-used oak beams.	SP 463028
1636	1634 /35 & 1635 /36	Midx	Richmond upon Thames	Hampton Court Palace	42.105 47.90 Oxf (35)	Real Tennis Court. 13.7m span 40m long roof designed by Inigo Jones. Wall plates scarfed at bay intervals. Short curved braces up to tiebeam, shouldered king posts [or king struts?], raking struts, 3 tiers of in-line tenoned purlins. (First repairs 1700 -32. 2nd repair phase 1747 -75. 3rd repair phase 1832 -53).	TQ 158685
1636	1634 /35 1635 /36	Shrop	Cherrington	Cherrington Manor	31.106 Oxf	Moated. Farmhouse. Triple-gabled. Lobby entry. Box-framed. Hewn jetty. Close studding with mid-rail & decorative framing.	SJ 666201
1636	1636	Suff	Ipswich	Isaac Lord Complex, 80 A Fore Street	34.94 MB CfA 76/2002	Merchant's House. (Also see 1418 -49, 1531 -49, 1587, 1540).	TM 168441
1636	1635 /36	Suss W	Lindfield	The Manor House	42.92 *LIMH/11/10*	3 storeys. 18thC exterior conceals 3-bay timber-framed bldg. Straight up-braces in wall. Dropped tiebeams, Principals, triple struts, staggered tenoned purlins.	TQ 347255
1637	1636 /37	Hamps	Netley Marsh	Winsor Manor Barn	40.125 Oxf	Barn, originally aisled. 5 bays. Straight braces from posts to *tiebeams*. *Raking struts* from tiebeams clasp the purlins.	SU 317138
1637	1636 1637	Hamps	Petersfield	Goodyers, The Spain	31.104 Oxf	Courtyard House: south range. Stone with brick dressings. Framed internal partitions, *tenoned purlins* roof. (Also see 1631 1632/3 & 1641/2).	SU 745241
1637	1619 -54	Notts	Langford-by-Home	Church	26.49 Notm	Nave roof.	SK 821590
1637	1621 -53	Oxf	Dorchester	The Abbey	35.99 Oxf	Re-used wind braces in a 19thC nave roof.	SU 579942
1637	1637	Oxf	Oxford	Oriel College	25.29 Oxf	Real Tennis Court. Oak posts, pine re-roofing. (Phase 2 dated to 1771-91).	SP 515061
1637	1634 /35 to 1637	Oxf	Oxford	84 St Aldates	44.105 Oxf	Timber-framed rear wing – 2 storeys, 5 bays. Dismantled in 2012 for reconstruction. (S wall framed storey-by-storey?)	SP 513058
1637	1637 +0	Staffs	Tamworth	95 Lichfield St	11.34 Sieb	King post trusses.	SK 203040
1637	1624 -49	Worcs	Worcester	Guildhall, High Street	39.126 Notm	Rebuilt 1722 -7 but it contains timbers with felling date ranges of 1624 -49, 1587 -1612 &c.	SO 849548
1638	1620 -55	Derbs	Shardlow	Moor Farm Cottage (N), London Rd	25.36 Notm	18thC brick cottage with re-used timbers in roof.	SK 428305
1638	1622 -54	Glouc	Huntley	Tuns Farm House	44.86 *GLTF/19/12*	Farmhouse. 2 bays. Timber-framed. Roof and 1st-floor timbers are replacements.	SO 717214
1638	1637 /38	Hamps	Winchester	Hyde Church	47.72 *SOHS/34/15*	Bell frame. (For tower see 1588 -1591).	SU481301
1638	1628 -48	Leic	Grimston	Church of St John the Baptist	37.117 Notm	Jack-braced bell frame with 4 trusses. (Replacement timbers 1759 -79?)	SK 685219
1638	1628 -48	Notts	Newark-on-Trent	5 Church Street	32.97 Notm	Building contains re-used timbers (of 1282 -1302 *qv*).	SK 798579

1638	1635 /36 1638	Oxf	Stanton St John	Manor Farm	29.114 Oxf	West range roof. Tiebeam & collar trusses with *queen struts* and clasped purlins. (Also see 1475).	SP 577095
1638	1622 -54	Sus W	Ardingley	Bolney Farmhouse, Selsfield Rd	35.101 Oxf	*Box-framed* N wing added to house of 1545 -50 (*qv*).	TQ 342305
1639	1621 -56	Derbs	Walton	Hipper Hall, Holymoorside	26.53 Notm	Surviving portion of cruck barn with type L1 apex.	SK 339695
1639	1638 1638 /39	Ess	Cressing	Timbers Barn	37.100 *CRTB/36/05*	2 bays. Jowled posts, straight braces.	TL 773204
1639	1639	Glouc	Wotton-under-Edge	Victoria Cottages, The Cloud	50.95 GLVC/29/18	Ex-situ lintel,	ST 760933
1639	1623 -55	Hamps	Winchester	The Deanery, Cathedral Close	49.138 MB DM	Panelling in room at W end of Long Gallery. Also see 1375 /76, 1499-1500, 1668)	SU 482291
1639	1638 -40	Lon	Chelsea	96 Cheyne Walk	47.89 MB DM	Dated pine ceiling beam (re-used?)	TQ 272776
1639	1639	Surr	Newdigate	Home Farm House	30.89 MB AML 37/98	Phase 4: rear range of building (first built 1351 *qv*).	TQ 207407
1639	1636 *c.* 1639	Surr	Ockham	Bridgefoot Barn	39.115 *RIBB/20/07*	The W.ern of 2 adjoining barns. Aisled, 3 bays, *queen struts*, clasped purlins. (For east barn see 1601 /02).	TQ 056569
1639	1638 /39 1639	Surr	Worplesdon	Frosbury Farmhouse	39.116 *FRWO/15/07*	2-storey porch *jettied* on 3 sides. (For farmhouse see 1550? and 1622).	SU 969519
1639	1638 /39	Warks	Wellesbourne	Granary, Chapel St	27.96 Oxf (36)	Granary with *stud and panel walls*.	SP 279551
1640	1620 -60	Derbs	Kirk Ireton	Kirk Ireton Church	26.54 Notm	Bellframe	SK 269502
1640	1626 -54	Glouc	Gloucester	Folk Museum, 103 Westgate St	48.85 *GLWS/18/16*	3 storeys, 2 bays, end chimneys. Now brick & stone, but 2nd floor timber framed, jettied. Small square panels, straight braces. Raking queen struts, straight wind braces, in-line tenoned purlins. (Also see 1509 and 1516).	SO 828187
1640	1628 -51	Lancs	Chorley	Buckshaw Hall, Euxton Lane	34.92 MB CfA 45/2003	Samples from a 'Building at Risk'.	SD 563202
1640	1640	Nort	Weston	Armada House, High Street	49.129 Notm	Significant fire damage. Two ranges at right-angle. This date is for truss with principal and collar in south range roof. (Pair of cruck blades did not date). (For north range see 1592 -1617 and 1487 -1512).	SP 591468
1640	1625 -55	Shrop	Neen Savage	Detton Hall	28.168 Oxf	Hall range: purlins were of 1779 /80. (Also see 1575 -76).	SO 666795
1640	1639 -41	Shrop	Stokesay	Stokesay Castle	28.161 Oxf (37)	Gatehouse. Walls – *close studding with mid-rail* and *down- braces* to ground floor: *jettied*: *small square panels* to 1st floor, with *lozenge work.*	SO 436816
1640	1627 -52	Som	Stogursey	Fairfield House	45.114 Notm RRS 35/2013	E-plan house. E range roof originally gabled, 6 trusses, principals, upper & lower collars, 3 tiers of side purlins + ridge piece. 'Connecting range', with roof timbers dated 1630 may be contemporary with E range: principals, single collars, 3 tiers of in-line tenoned purlins + ridge piece. (For W range see 1508 -28, for replacement hips see 1779).	ST 187429
1640	1639 -1640	Suff	Cratfield	St Mary's Church	40.106 MB	Timbers in bellframe thought to date to 16thC.	TM 313748
1640	1612 -44 1624 -56	Wilts	Clarendon	Dog Kennel Park Farm	35.102 Oxf	Timbers employed in construction of inserted attic floor (in building of 1588 1588/9}.	SU 170286
1641	1625 -57	Ess	Great Leighs	Lawns Farmhouse	35.98 Oxf (38)	Single timber from S range. (Also see1538 -52).	TL 740138
1641	1634 to 1641 *c.*	Hamps	Hook	Lee's Farm Cottage, London Road	51.119 *RGCF.07/19*	2½ bay central chimney house. Gabled. Small square panel walls, unjowled posts. Queen struts, clasped purlins, diminished principals, straight wind-braces.	SU 729546
1641	1641	Shrop	Shrewsbury	Abbey Church	31.117 UoW AML 39/99	Belfry tower. Re-used timbers dated 1493 and secondary roof timbers dated 1641 were found in the tower. (Primary timbers in roof dated to 1380-1395 *qv*).	SJ 506122
1641	1640 /41	Suss E	East Grinstead	Old Stone House, High Street	32.84 Oxf	*Stone* wing added to Clarendon House (*qv*). It contains an excellent oak newel staircase.	TQ 394379
1642	1635 -49	Dur	Durham	Bull Hole Byre, Bearpark	34.105 Notm CfA 111/2002	Byre and cart-shed. *Stone*. Two pairs of [*cranked*] crucks with *extended collars* for the purlins, and pegged *saddles* carrying ridge-piece.	NZ 233422

1642	1637-46	Glouc	Saint Briavel's	Saint Briavel's Castle	33.107 Notm AML 42/99	Re-used timbers used to re-roof gatehouse west tower. Sole-plates once thought primary to walls of *c.*1293 had a felling date range of 1516-66. (Also see 1592).	SU 559046
1642	1641 /42	Hamps	Petersfield	Goodyers, The Spain	31.104 Oxf	Courtyard House: south-east range. (Also see 1631 1632/33 &.1636 1637).	SU 745241
1642	1641 /42	Shrop	Wem	Aston House, Aston	49.127 *AYAH/32/17*	2½-storey H-plan house with lateral chimneys at each end of central range. Walls 3 & 4 small rectangular panels high. Roofs have queen-struts, trenched purlins, straight wind-braces. Wing gables jettied at 1st-floor and attic levels.	SJ 529286
1642	1626 -58	Surr	Capel	Taylors, Rusper Road	35.81 *CATA/36/03*	3-bay, 3-storey *jettied* wing added to open hall of 1454 -80 (*qv*). *Small square panel* framing with unjowled posts. *Dropped tiebeams* on third storey. *Queen struts*, clasped purlins, no wind braces.	TQ 182387
1642	1641 /42	Surr	Charlwood	2 Old Rosemary Cottage, Rosemary Lane	32.83 Oxf	Two-bay cottage, the small end-bay with a *smoke bay*. *Small panels*, *straight braces*, no jowls.	TQ 244412
1642	1641 /42	Warks	Baddesley Clinton	Baddesley Clinton (Nat Trust)	33.86 Oxf (39)	Reconstruction of roof over west half of south range. Tiebeams: *raked struts* to clasped side purlins, i.e. no collars. (Also see 1702 etc).	SP 200715
1643	1643 /44	Beds	Bletsoe	2-3 Old Way	38.119 Oxf	Timber in floor inserted into open hall (of 1459 /60 *qv*)	TL 022581
1643	1640 -45 *c.*	Derbs	Killamarsh	Westhorpe Farm, Westhorpe Road	25.41 Notm	Tiebeam & collar trusses, double side purlins. Fragments of *smoke-hood* in roof space.	SK 455799
1643	1630-55	Dur	Heighington	Manor House	43.89 Notm RDRS 11/2012	Hearth-passage plan. Front range roof – 3 principal rafter trusses with tiebeam & collar, 2 tiers of trenched purlins. Rear wing – 1 tiebeam & principal truss (no collar), 2 tiers of trenched purlins.	NY 251224
1643	1630 -55	Numb	Hexamshire Low Quarter	Linnels Mill	45.113 Notm RRS 32/2013	1 lintel has fdr of 1630-55. (For water-driven fulling mill roof timbers see 1712 -13).	NY 951614
1643	1630 -1655	Staffs	Shobnall	Sinai Park	30.90 Notm	Central block inserted between two older parallel ranges. (Also see 1676-1701).	SK 223232
1643	1643 +	Wilts	Clarendon	The Old Mansion	31.127 Sh	Ground-floor beams.	SU 195285
1643	1640 -45	YksWR (YksW)	Whiston	The Long Barn, Chaff Lane	33.117 Sh	First built with timber felled 1233 -52 (*qv*), but an extension, and the entire roof may derive from this later phase, employing 3 different forms of truss.	SK 447901
1644	1631 -56	Heref	Moccas	New House Farm Barn	45.110 Notm	Barn: tiebeam and collar. (For house see 1584).	SO 356402
1644	1637 1644	Shrop	Bolas Magna	Meeson Hall	27.103 Oxf	Inscribed date matches dendro?	SJ 658207
1644	1641 /42 1643 /44	SusW	East Grinstead	Charlwood Farm	43.86 *EGCF/11/11*	House. Timber-framed, 3½ bays. Large square panels, unjowled wall posts. Main range roof replaced?	TQ 393342
1644	1628 -60	SusW	East Lavant	Borrans, 41 Pook Lane	43.87	2 storeys, now brick. No roof details.	SU 857079
1645	1645	Bucks	Ickford	The White Cottage, 2 Bull's Lane	49.136 MB DM	Floor inserted into S bay of 3-bay house. (For re-used cruck blade see 1383, and for primary cruck phase with open central bay see 1584).	SP 653071
1645	1645	Glouc	Gloucester	The Fleece Hotel, 19 Westgate Street	48.111 Oxf RRS 36/2017	This date is for undercroft ceiling. (For Westgate range see 1472 and for main range see 1476).	SO 831185
1645	1635 -55	Leic	Ashby Parva	Church of St Peter	37.116 Notm	Jack-braced oak bell frame.	SP 525887
1645	1645	Norf	Forncett	Riverside Farm	42.94 IT	3-bay timber-framed building originally with framed chimney. 'Queen post roof' [or queen strut?] King strut in service bay wall. Wall plate has face-halved scarf joint.	TM 167944
1645	1645	YksWR (YksN)	York	60 Stonegate	31.127 Sh	Repairs / remodelling of a building (of 1322 /23 *qv*).	SE 602521
1646	1646	Hamps	Priors Dean	Goleigh Manor	28.176 Oxf	Hall (of 1466 *qv*) partly reconstructed shortly after 1646.	SU 743313
1646	1626 /27 1631 -61	Shrop	Lydbury North	Long Thatch	38.133 Oxf	Western extension to house (of 1557 -71 *qv*). Inserted floor in cruck range dated 1616 -25 1624 -51 probably done at same time as extension.	SO 351861
1646	1645 /46	Shrop	Moreton Corbet & Lee Brockhurst	The Wain House	49.126 *SYWH/04/17*	2-bay main range with central chimney. Walls 3 small square panels high, jowled posts. Queen-strut roof with 2 tiers of trenched purlins and straight wind-braces. Replaces earlier hall range? (For N wing see 1578 -1608).	SJ 529269
1646	1646	Warks	Middleton	Middleton Hall	37.115 Notm	De Freville building (east range). *Box framed*, *square panels*.	SP 192980

1647	1646 /47	Hamps	Old Basing	Parkers Piece Barn, Crown Lane	46.108 Oxf	Aisled brick barn with hipped roof. Threshing bay roof trusses have 'raking queen posts' up to purlins but hip trusses have vertical queen struts, collars.	SU 667527
1647	1646 /47	Kent	Charcott	Jessops	43.84 THJO/17/11	Chimney inserted into open hall house (of *c.*1398 qv).	TQ 523471
1647	1628 -56	Lancs (GrMan)	Birkdale	The Cottage, 74 Liverpool Road	31.125 Sh AML 20/2000	Two-bay cruck house with later box-framed extension.	SD 332154
1647	1647	Notts	Epperstone	Church of the Holy Cross	47.85 Notm	Jack-braced bell frame.	SK 650485
1647	1646 1647	Oxf	Stanton St John	Manor Farm	29.115 Oxf	Stables. *Stone*. 'Straight inner principals'	SP 577095
1647	1646 /47	Shrop	Clunbury	Yews Cottage	37.128 Oxf	*Jettied* rear range. *Box-framed*. Small struts from tie to principals, *trenched purlins*.	SO 371805
1647	1637 -57 1607 -37	Shrop	Lydbury North	Gravenor House	38.132 Oxf	*Box-framed*, later encased in stone. Box-framed gabled wing not sampled. (Re-used timbers dated 1433).	SO 349860
1647	1646 -47	YksWR (YksS)	Eckington	Old Kent House, Ridgeway	21.44 Sh	No roof details. (Also see 1602 -46).	SK 403818
1647	1645 -47 1647 /48	Wilts	Devizes	4-5 St John's Alley	21.47 Oxf	Cellar + 3 storeys + attic. Industrial? Jettied. Poor construction: nailed studs and rails. Staircase with timbers dated from 1645 to 1647 /48, apparently an early insertion.	SU 005614
1648	1640 /41 to 1648	Bucks	West Wycombe	Crown Court, High St	44.101 Oxf	In No. 35 – bays W of carriage arch – beams & floor joists. (Also see 1542 /43 & 1561).	SU 831946
1648	1630 -65	Dur	Durham	Old Durham Farm	26.55 Notm	5 truncated principal struts with straight members throughout: double side purlins. (Also tiebeams of 1665 -62+20).	NZ 288419
1648	1648	Lincs	Lincoln	Chad Varah House	39.108 Notm	Re-used timbers of various dates inc. 1660 -85.	SK 976717
1648	1647 /8	Oxf	Stanton St John	Manor Farm	29.115 Oxf	Barn. *Stone*. Tiebeams, *queen struts*, interrupted collars at 'princess struts'. Two tiers of clasped purlins.	SP 577095
1648	1647 /8 1648	Surr	Worplesdon	Frosbury Farmhouse	40.109 *FRWO/16/08*	Two-storey scullery bay. *Brick*, *gabled*. *Queen struts*, clasped purlins, no wind-braces. Also a floor of 1621 /2 inserted into a smoke bay. (Also see 1550? and 1622).	SU 969519
1649	1648 /49	Notts	Fledborough	Church of St Gregory	47.85 Notm	Jack-braced bell frame.	SK 481372
1649	1648 /49	Surr	Charlwood	Greenings Farm Barn	36.76 *CHGB/07/04*	One bay added to threshing barn of 1538 1538 /39 *qv*). *Queen struts*, clasped purlins, wind braces.	TQ 225416

ACKNOWLEDGEMENTS

Dr Dan Miles is thanked for identifying an error on an earlier version of this table.

REFERENCES

[1] M Moran *Vernacular buildings of Shropshire* (2003), 223-225.
[2] K Rodwell 'The architecture of entertainment: two examples of a late sixteenth-century building type', *Archaeol. J.* 148 (1991), 269 -95.
[3] VAG Spring Conference Programme (2001), 9.13
[4] F W B Chalres & M Charles *Conservation of timber buildings* (1984), 46, 47, 230-233.
[5] E Roberts 'The Old Manor, Ashley, Hampshire – tree ring dated to 1521, 1529/30 and 1605/06', *VA* 28 (1997), 115;
Roberts et al *Hampshire houses 1250-1700: their dating and development* (2003), 152-3.
[6] D Andrews (ed) *Discoivering Coggeshall* 2 (2013), 104-107.
[7] T G Jackson *Wadham College Oxford* (1893), 29-49.
[8] R A Meeson and N W Alcock *Hall's Croft, Stratford upon Avon: an architectural survey and history* (June 1998), 17-18.
[9] R A Meeson and N W Alcock *Hall's Croft, Stratford upon Avon: an architectural survey and history* (June 1998), 18-20.
[10] D. Stenning 'East Anglian roofs ...' in J. Walker (ed) *The English medieval roof: crown post to king post* (2011), 46.

[11] *J. Norfolk Hist. Bldg. Group* 3 (undated?), 46-62.
[12] D Zeuner (ed) *Building History: Weald and Downland Open Air Museum* (2010), 107.
[13] S Price *26 Westgate Street, Gloucester* (1994)
[14] D Andrews (ed) *Discovering Coggeshall* 2 (2013), 139-149.
[15] D Zeuner (ed) *Building history. Weald and Downland Open Air Museum 1970-2010 – the first forty years* (2010), 97.
[16] N A Hill 'Crucks on the edge: the East Midlands', in Alcock, Barnwell and Cherry (eds.) *Cruck building: a survey* (2019), 142-7.
[17] M Moran *Vernacular buildings of Shropshire* (2003), 215-17.
[18] B Harrison and B Hutton *Vernacular houses in North Yorkshire and Cleveland* (1984), 20-23.
[19] P. Ryder *Canons Garth, Helmsley: an historic building assessment* (2012).
[20] VAG Spring Conference Programme Devon 2008, 1.14-1.15.
[21] T. Howson 'A cottage with anchor beams …', *Essex Historic Buildings Group n.l.* 8 (2011), 3-7.
[22] R Heawood, C Howard-Davis, D Drury and M Krupa *Old Abbey Farm, Risley: building survey and excavation at a medieval moated site* (Oxford Archaeology North, 2004).
[23] A. Arnold and R. Howard *Horton Hall, Horton, near Leek, Staffordshire; tree-ring analysis of timbers* (2015).
[24] Bob Meeson *Bretby Hall, Derbyshire: archaeological watching brief 1998-2003* Rep. No. 03/17, December 2003.
[25] C Rosier, N R Fradgley and N J Williams 'Cogges Manor Farm, Witney, Oxfordshire, 1554/5', *VA* 27 (1996), 69.
[26] N W Alcock and R A Meeson, 'Baddesley Clinton: architectural responses to social circumstances', *Antiq J* 87 (2007), 295-345
[27] R A Meeson and N W Alcock *Hall's Croft, Stratford upon Avon: an architectural survey and history* (June 1998), 25-27
[28] B Harrison and B Hutton *Vernacular houses in North Yorkshire and Cleveland* (1984), 20-23.
[29] P. Ryder *Canons Garth, Helmsley: an historic building assessment* (2012).
[30] N W Alcock 'Devon farmhouses pt. 2: some Dartmoor houses', *Rep. Trans. Devonshire Assoc*., 101 (1969), 83-106.
[31] J Ashdown, I Fisher and J Munby 'The roof carpentry of Oxford Cathedral', *Oxoniensa*, 53 (1988), 195-204.
[32] N Hill 'Hall and chambers: Oakham Castle reconsidered' *Antiq. J.* 93 (2013), 163-216
[33] Bob Meeson *Hardwick Old Hall East Lodge: roof survey during works in 1999* Rep No 00/04 (2000)
[34] D Andrews (ed) *Discovering Coggeshall* 2 (2013), 158-166.
[35] L Prosser 'Inigo Jones and tennis', *Soc. of Architectural Historians of Great Britain Newsletter* 104 (Autumn 2011), 1-3.
[36] N W Alcock and D H Miles 'A stud and panel granary in Warwickshire' *VA* 27 (1996), 38-39.
[37] M Moran *Vernacular buildings of Shropshire* (2003), 203-206.
[38] VAG Spring meeting programme (2003) ...
[39] N W Alcock and R A Meeson, 'Baddesley Clinton: architectural responses to social circumstances', *Antiq J* 87 (2007), 295-345